

Approved as to
form only:

ORDINANCE NO. _____

Date: 5/9/18

ENTITLED: "AN ORDINANCE PURSUANT TO SECTION 2.2.1 ZONING MAP AMENDMENTS, SECTION 2.2.2 PLANNED DEVELOPMENT PLAN, SECTION 5.1.2 ZONING DISTRICTS ESTABLISHED, SECTION 5.1.3 OFFICIAL ZONING MAP, AND SECTION 5.6.2. PUD – PLANNED UNIT DEVELOPMENT DISTRICT, OF THE UNIFIED DEVELOPMENT CODE, CHANGING THE ZONING CLASSIFICATION FROM LARAMIE COUNTY SWEETGRASS PLANNED UNIT DEVELOPMENT (PUD) TO CITY OF CHEYENNE SWEETGRASS PUD FOR 2,349.54 ACRES OF LAND KNOWN AS THE SWEETGRASS LAND AREA, CITY OF CHEYENNE, LARAMIE COUNTY, WYOMING (LOCATED SOUTH OF COLLEGE DRIVE AND EAST OF AVENUE C)."

BE IT ORDAINED BY THE GOVERNING BODY OF THE CITY OF CHEYENNE, WYOMING:

Section 1. That the owners of the property described herein have submitted a Sweetgrass Planned Unit Development ("PUD") Preliminary Plan pursuant to Section 5.6.2.f of the Cheyenne Unified Development Code ("UDC") which was conditionally-approved by the Governing Body on October 10, 2016.

Section 2. That on May 7, 2018, the City of Cheyenne Planning Commission conducted a public hearing, reviewed the Applicant's proposed Sweetgrass PUD Final Plan that is the subject of this ordinance, found that it met the three conditions of approval of the PUD Preliminary Plan, and recommended conditional-approval of said PUD Final Plan, rezoning the property described herein to Sweetgrass Planned Unit Development-PUD.

Section 3. That the Governing Body of the City of Cheyenne finds that the PUD Final Plan that is the subject of this ordinance meets the criteria specified in Section 2.2.1.d of the UDC.

Section 4. That, in accordance with Section 2.2.1, Zoning Map Amendments, Section 2.2.2, Planned Development Plan, Section 5.1.2, Zoning Districts Established, Section 5.1.3, Official Zoning Map, and Section 5.6.2 PUD – Planned Unit Development District, of the UDC, the application is hereby approved, and the zoning classification of the real property described in Exhibit A to this ordinance is hereby changed to Sweetgrass Planned Unit Development (PUD).

Section 5. That, in accordance with Section 5.6.2, the land use, design and development standards and guidelines described in Exhibit B to this ordinance shall govern this PUD zoning classification.

Section 6. That the City Engineer is hereby authorized and directed to alter and amend the Official Zoning Map as described in 5.1.3 of the UDC to comply with the zone change as described in Section 4 above when this ordinance takes effect in accordance with Section 8 below.

Section 7. Sections, paragraphs, sentences, clauses and phrases of this ordinance are severable. If any section, paragraph, sentence, clause, or phrase of this ordinance is declared unconstitutional, such unconstitutionality shall not affect any of the remaining sections, paragraphs, sentences, clauses, and phrases.

Section 8. That this ordinance shall be in full force and effect upon its approval and publication.

FIRST READING: _____

SECOND READING: _____

THIRD AND FINAL READING: _____

MARIAN J. ORR, MAYOR

(SEAL)
ATTEST:

CAROL INTLEKOFER, CITY CLERK
publish date: _____

EXHIBIT A: Sweetgrass PUD Legal Description

Legal Description:

The following parcels of land situated in Township 13 North, Range 66 West of the 6th P.M., Laramie County, Wyoming, described as follows:

The Southeast Quarter of the Southeast Quarter (SE $\frac{1}{4}$ SE $\frac{1}{4}$) of Section 10; the South Half of the South Half of the West Half (S $\frac{1}{2}$ S $\frac{1}{2}$ W $\frac{1}{2}$) of Section 11; the West Half (W $\frac{1}{2}$) of Section 14; all of Section 15; all of Section 16 lying south of College Drive right-of-way line and EXCEPT that parcel recorded June 26, 1991 by Warranty Deed filed in Book 1304, Page 1805, Laramie County, Wyoming, records described as follows:

Beginning at a point on the West line of said Section 16, from which the Northwest corner thereof bears N.0°50'32"E., a distance of 1320.58 feet; thence S.89°42'54"E., a distance of 160.00 feet; thence S.0°50'32"W., a distance of 160.00 feet; thence N.89°42'54"W., a distance of 160.00 feet to a point on the West line of said Section 16; thence N.0°50'32"E., along said West line, a distance of 160.00 feet to the point of beginning. Exception containing 0.5877 acres more or less; and all of Section 21, Cheyenne, Wyoming.

EXHIBIT B: Sweetgrass Final Planned Unit Development Standards and Guidelines
Printed April 23, 2018 and Adopted _____.

CITY COUNCIL STAFF REPORT - SUMMATION

Sweetgrass PUD Final Plan

CASE NUMBER(s): UDC-18-00105

SUBDIVISION CODE: SWET

PREPARED BY: Susana Montana

MEETING DATES: May 7, 2018 – Planning Commission
May 14, 2018 – City Council (1st read)
May 22, 2018— Public Services Committee (1st read)
May 29, 2018— City Council (2nd read)
June 5, 2018 – Public Services Committee (2nd read)
June 11, 2018—City Council (3rd review and Final Action)

REQUIRED DOCUMENTS SUBMISSION: The following required documents have been submitted and reviewed by staff.

- Master Application Form signed by Owner Representative and Agent
- Planned Unit Development (PUD) Maps
- Planned Development Standards and Guidelines (Regulations)
- Project Site Legal Description
- List of Adjacent Property Owners

RECOMMENDATION: On May 7, 2018, the Planning Commission recommended **conditional-approval** of the Sweetgrass Planned Unit Development (PUD) Final Plan with the following condition:

1. The Applicant shall amend the Sheet 6 PUD Master Trail Plan Map to reflect the greenway routes/alignment approved by the City's Community Recreation and Events Department.

CITY COUNCIL STAFF REPORT

Sweetgrass PUD Final Plan Planned Development – Regulating Plan Process

CASE NUMBER(s): UDC-18-00105

SUBDIVISION CODE: SWET

PREPARED BY: Susana Montana

MEETING DATES: May 7, 2018 – Planning Commission
May 14, 2018 – City Council (1st read)
May 22, 2018— Public Services Committee (1st read)
May 29, 2018— City Council (2nd read)
June 5, 2018 – Public Services Committee (2nd read)
June 11, 2018—City Council (3rd review and Final Action)

OWNER: Sweetgrass Ranch, LLC (307) 630-5050
1825 Campstool Road
Cheyenne, WY 82007

AGENT: Lee Martin (970) 667-6286
3521 W. Eisenhower Blvd.
Loveland, CO 80537

PROJECT: Sweetgrass PUD Development Master Plan

WORK DESCRIPTIONS: A regulating plan for the Sweetgrass Planned Unit Development (PUD) master planned community.

LOCATION:

Legal Description: The following parcels of land situated in Township 13 North, Range 66 West of the 6th P.M., Laramie County, Wyoming, described as follows:

The Southeast Quarter of the Southeast Quarter (SE $\frac{1}{4}$ SE $\frac{1}{4}$) of Section 10;
the South Half of the South Half of the West Half (S $\frac{1}{2}$ S $\frac{1}{2}$ W $\frac{1}{2}$) of Section 11;
the West Half (W $\frac{1}{2}$) of Section 14;
all of Section 15;

all of Section 16 lying south of College Drive right-of-way line and EXCEPT that parcel recorded June 26, 1991 by Warranty Deed filed in Book 1304 Page 1805, Laramie County, Wyoming records described as follows: Beginning at a point on the West line of said Section 16, from which the Northwest corner thereof bears N.0°50'32"E., a distance of 1320.58 feet; thence S.89°42'54"E., a distance of 160.00 feet; thence S.0°50'32"W., a distance of 160.00 feet; thence N.89°42'54"W., a distance of 160.00 feet to a point on

the West line of said Section 16; thence N.0°50'32"E., along said West line, a distance of 160.00 feet to the point of beginning. Exception containing 0.5877 acres more or less; and all of Section 21, Cheyenne, Wyoming.

Location: South of College Drive and east of Avenue C.

Address: Un-addressed

SIZE: 2,3450 plus or minus-acres

CURRENT ZONING: County Sweetgrass PUD

PROPOSED ZONING: Sweetgrass PUD

EXISTING LAND USE: Cattle grazing/ranching

PROPOSED LAND USE: A mixed use community of up to 5,000 dwelling units, 195.5-acres of commercial development, school sites, parks and open space for up to 4.4 Million square feet of non-residential building area.

SURROUNDING LAND USES:

SURROUNDING	LAND USE(S)	ZONING	ANNEXATION STATUS
North east	Cattle grazing	City AG- Agricultural (Read-Lummis rezoning)	City (Read-Lummis Annexation)
North west	Laramie County Community College	County PUD	County
South	Cattle grazing	County Agricultural A2-	County
East	Cattle grazing	County Agricultural A2-	County
West	Manufactured home parks; rural residential lots, mini-storage units	County Mixed Use, Light Industrial & Community Business	County

EXECUTIVE SUMMARY:

The proposed Sweetgrass Planned Unit Development (PUD) Final Plan application is the subject of this report. A Sweetgrass Preliminary Plan was submitted for Planning Commission and City Council (Governing Board) review and approval in October 2016, pursuant to Section 5.6.2 of the City's Unified Development Code (UDC). The PUD Preliminary Plan was conditionally-approved by the City Council in 2016 with the following three conditions to be addressed with the Final PUD submittal.

1. A Transportation Impact Study (TIS) and a Transportation Network Plan (TNP) based on the TIS findings shall be included with the Sweetgrass PUD Final Plan and Zoning Map Amendment applications;
2. A Community Facilities Impact Assessment shall be included with the Sweetgrass PUD Final Plan and Zoning Map Amendment applications; and
3. An exhibit detailing public and private trail locations and maintenance thereof shall be submitted with the Final PUD.

This PUD Final Plan submittal includes the TIS, Community Facilities Impact Assessment document, and a revised Trails Master Plan map; all of which satisfy the conditions of approval of the PUD Preliminary Plan.

This PUD Final Plan submittal represents a zoning map amendment action pursuant to Section 2.2.1 of the UDC, a Planned Development Regulating Plan pursuant to Section 2.2.2 of the UDC, as well as the PUD Final Plan pursuant to Section 5.6.2.g of the UDC. The evaluation of this PUD Final Plan submittal will follow and addresses the 15 review criteria of Section 2.2.2.d of the UDC for PUD Regulating Plans.

In summary, this PUD Regulating Plan submittal generally meets the content requirements of Section 2.2.2 in that it consists of the development standards and regulations for new development that would take place within the 2,350-acre PUD Site over a period of decades. At full build-out, the PUD regulations would allow 5,000 new dwelling units and around 195-acres of commercial or non-residential space which could result in up to 4,400,000 (4.4 Million) square feet of office, retail, entertainment and service uses. This represents a new community for the City of Cheyenne on former agricultural land to which the City can extend public services and infrastructure in a timely and cost-efficient manner.

The PUD Site consists of historic cattle grazing rangeland and the PUD regulations would enable this activity to continue on the Site on undeveloped lands until gradual build-out of the Sweetgrass PUD community causes this activity to retreat to the remaining rangeland of the Lummi ranching operation. The Lummi family corporate entity named Sweetgrass Ranch LLC is the "Applicant"

for this Sweetgrass PUD Final Plan and this report refers to the corporation as the Applicant. However, the City recognizes that the Applicant entity actually consists of many generations of family members who are concerned with the quality of development of the new Sweetgrass community taking place on their heritage rangeland.

As noted below, the Sweetgrass PUD regulations and land use designation map appear to guide development of this mixed-use community in a way that would result in a master planned community of over 12,000 residents and workers. The application includes an impact assessment of the public services needed to properly serve this new population located at the edge of the City, now that the Site has been annexed into the City. The Assessment assumes that the impact fees and parks and infrastructure fees outlined in the Sweetgrass PUD Annexation Master Annexation Agreement, adopted and executed in February 2018, will assist the City, Applicant and individual developer(s) in funding the roads, water, sewer, police, fire, emergency medical service, parks, public works, sanitation, and other essential services, that are needed by this new community.

The PUD Final Plan, pursuant to UDC Section 5.6.2.g, must be evaluated by the review criteria of UDC Section 2.2.2.d. (Planned Development – Regulating Plan or Development Master Plan) and this report contains that evaluation. Each of the 15 review criteria are important measurements as to how the proposed development would be consistent with City policies, would be compatible with surrounding developments, what quality of development would result within the PUD land area, and how the City would provide essential services to the new development. The proposed Sweetgrass PUD Final Plan positively addresses those 15 review criteria as noted below.

Therefore, with the following Planning Commission-recommended condition of approval, the proposed Sweetgrass Planned Unit Development Final Plan maps and regulations would meet the review criteria of Section 2.2.1.d, 2.2.2.d, and 5.6.2.g of the Cheyenne Unified Development Code. On May 7, 2018, by a vote of 4 to 0, the Planning Commission conditionally-approved this PUD Final Plan application, advancing it to the Governing Body with the following condition:

1. The Applicant shall amend the Sheet 6 PUD Master Trail Plan Map to reflect the greenway routes/alignment approved by the City's Community Recreation and Events Department.

SWEETGRASS PUD LOCATION/VICINITY MAP:




Figure 1 – Project Location/ Vicinity Map
Source: Cheyenne/Laramie County GIS Cooperative Program



Figure 2 – View east of Site from Avenue C
Source: Development Department

and welfare. Design excellence and the provision of outstanding public amenity shall be considered when establishing development standards of the PUD.

In reviewing, providing comments, and making recommendations and decisions on a proposed PUD Preliminary Plan, the Staff, Planning Commission and City Council shall use the following **15 criteria** of Section 2.2.2.d:

1. *The application meets all threshold requirements for application of the PUD District or Form-based Code standards.*

Complies. The threshold requirements for application of a PUD District are found in Section 5.6.2 of the UDC and include the following: (1) A minimum size of 2 acres; (2) a Sketch Plan detailing the Applicant's intent; and (3) a Preliminary Plan containing concepts, standards and phasing for the full build-out of the subject property.

Those requirements have been met by the PUD Preliminary Plan and by this PUD Final Plan. The PUD regulating text describes the development standards and guidelines for development within the PUD land area and incorporates by reference portions of the City's UDC. In particular, Section 1, General Provisions, Subsection B (Application).4 of the PUD regulations states: "*Portions of the PUD are more stringent than the UDC; others are less stringent and/or provide a different approach. If the PUD does not address a specific item, the most current edition of the Cheyenne UDC shall govern; otherwise, this PUD shall govern.*" Therefore, where the PUD regulating document is "silent" on a normal development standard and regulation, the PUD text defers to the UDC standards in effect at the time of a plat or permit application. The PUD regulations are "silent" on about 40 UDC standards, such as home occupation uses or accessory dwelling unit standards; therefore, permit applications for those uses or structures would be measured by the applicable UDC standard in effect at the time of the permit application submittal.

These provisions make the PUD regulations dynamic and able to reflect changing community values and market forces. PUD subsection H outlines procedures for amendments to the PUD regulations which would also ensure that the PUD standards reflect changing development methods, market forces and community design values.

The PUD Final Plan includes a land use map (Sheet 3 of Attachment A Maps) showing generalized areas of streets, trails, development sub-areas ("parcels") of varying densities, and lands to be made available for open space, school sites, and a City park.

2. *The application presents clear and specific criteria on how the property and subsequent development will be reviewed, regulated and modified consistent with these regulations.*

Complies. See also the evaluation of Criterion 1 above.

The PUD regulation document, presented herein as Attachment A, identifies how each parcel within the 2,350-acre the master planned community would be developed and maintained. The majority of the private common lands, such as trails, open space, landscaping and private streets located within neighborhoods, would be maintained by a central Homeowners Association (HOAs) and/or smaller neighborhood-based HOAs. Public streets, some greenway trails, and the Community park would be owned, developed, operated and maintained by the City of Cheyenne. However, because the development of this City park would be funded by park enhancement fees paid by each plat developer, it would be developed incrementally as land is developed and these fees are paid.

A development agreement, called the Sweetgrass Annexation Agreement, between the Applicant and the City, was informed by the transportation impact study and the community facilities impact assessment, and has been adopted by the City Council and executed by the Mayor and Sweetgrass land owners.

The PUD regulation document incorporates by reference 43 UDC standards and regulations. The current submittal does not list those UDC sections in a clear table or fashion. In order to make review of development proposals, building permits or subdivision plats most efficient, staff needs those sections clearly identified in a separate appendix or table. Therefore, staff is recommending Condition Number 1 which would require the PUD Standards and Guidelines to include an Appendix B listing which UDC standards are incorporated by reference into the document. This would allow land owners, prospective buyers, tenants and other prospective Applicants to be aware of what rules their project would be measured by. It would also ensure that City staff is reviewing the application by the proper regulations.

3. *The application is in accordance with the development policies and physical patterns identified in the Comprehensive Plan.*

Complies. There are numerous PlanCheyenne policies and principles that the proposed PUD positively addresses. Some of these comprehensive plan policies and

principles are noted below and others are noted in the PUD Preliminary Plan staff report (UDC-16-00509) which is incorporated by reference herein.

Future Land Use




Figure 4 – PlanCheyenne Future Land Use Map
Source: Cheyenne/Laramie County GIS Cooperative Program




Figure 5 – Enlarged Area PlanCheyenne Future Land Use Map
Source: Cheyenne/Laramie County GIS Cooperative Program

Land Use Designations

The majority of the PUD Site lies within the PlanCheyenne future land use map designation of **Urban Residential (UR)**. The northern portion adjacent to the LCCC campus is designated both **Mixed Use Residential Emphasis (MUR)** and **Mixed Use Commercial Emphasis (MUC)**. Land to the east of the LCCC campus is designated both **Open Space (OS)** and **Mixed Use Employment Emphasis (MUE)**. A portion of the southeastern portion of the Site is designated **Rural Residential (RR)**. The ways in which the PUD addresses those designations are noted below.

Urban Residential Designation

The following are the PlanCheyenne desired characteristics of the Urban Residential land use type.

Develop in traditional development patterns with a mix of densities, lot sizes, housing types, and home sizes that are well integrated with one another.

- Provide a wide variety of housing types, lot sizes, styles, and patterns in new urban developments.*

- Include well planned amenities such as parks and open space that is usable and/or connected. Design the core of an urban residential neighborhood to contain apartments and townhomes and may even include neighborhood retail uses organized around a public space that is inviting for pedestrians.*

- Integrate secondary uses that to serve the neighborhood and develop and operate them in harmony with the residential character.*

- Design streets and sidewalks to provide connections to, from, and within the neighborhoods to make it safe and convenient for people to walk and ride bicycles.*

- Connect to central water and sewer utilities.*

- Provide paved streets with sidewalks.*

- Establish transitions between different intensities or activities. For example, lower density residential (e.g., with a minimum of four dwelling units per acre and ranging up to six du/acre) is appropriate away from shopping and other activity centers and should be accessed from local or collector streets. For these areas, some common open space should be provided.*

• *Provide common open space or other private amenities, such as tot lots, playground or gardens/courtyards, in multi-family residential areas.*

• *Step down building heights where multi-family development is adjacent to lower density development, so that no building is 150% taller than an adjacent building, and provide open space buffers.*

Staff Evaluation: ***Complies.*** The proposed PUD regulations and land use map would guide development to achieve the desired characteristics for the Urban Residential designated lands. Seven internal streets connect to the western neighborhoods: Murray Road, East Nation Road, Wallick Road, Stratus Road, Pontillo Road, Boreas Drive, and High Plains Road.

Open Space Designation.

The eastern portion of the PUD Site is designated as Open Space. The PlanCheyenne desired characteristics for Open Space are as follows:

- *Public and private open space, public and private parks, country clubs, and golf courses are appropriate uses. Some public utilities or facilities may also be appropriate. This category may also include a natural/cultural resource area.*
- *Open space includes public sites and areas for active and passive recreation, conservation and mitigation of environmental hazards. The location, access, terrain, size, and design will vary for future open space, depending on the specific use.*

Staff Evaluation: ***Complies.*** The PUD land use map identifies large parcels of the eastern portion of the Site for a golf course with some low and very low residential densities. The residential lots would be oriented toward adjacent open spaces or the golf course.

Mixed Use Commercial Emphasis Designation.

The desired characteristics for that land use are as follows:

Create an environment that has employment opportunities and shopping opportunities, a range of housing types and parks, open space and civic uses, if appropriate,

- *Mix uses either vertically or horizontally.*
- *Develop in an integrated, pedestrian friendly manner.*
- *Provide building height transitions and step-downs to be compatible with adjacent development.*
- *Do not dominate the area with any one land use or housing type.*

Staff Evaluation: ***Partially Complies.*** The northern portion of the PUD land use map designates six areas for commercial/non-residential development which would provide employment opportunities for City residents, for LCCC students, and for Sweetgrass residents who could walk or bike to work. The commercial activities could include a shopping center, a village retail/office/public facilities center, another retail center, two parcels for hospitality/event centers, and a medical office campus.

The PUD regulations contain specific design and development standards for this commercial development. The regulations do not specify a maximum amount or square footage for any one commercial land use or activity type. Rather, it appears to allow market forces to determine how much retail, office and service uses would develop within the six areas. However, the goal of the “village center” commercial node is to provide businesses that would serve LCCC students, faculty, other workers and visitors as well as residents of Sweetwater PUD.

The northern commercial areas do not provide any housing and for this reason the PUD only partially complies with the MUC designation of PlanCheyenne.

Mixed Use Residential Emphasis Designation.

The northeastern portion of the PUD is designated Mixed Use Residential Emphasis (MUR) which seeks to provide a range of residential housing types as well as a mix of retail, offices and light trade uses. The desired characteristics of the MUR includes:

- *Provide a vertical or horizontal mix of uses on sites, including some multi-family residential.*
- *Integrate residential townhomes and apartments and other more urban development, generally in the core (highest-intensity area) of the mixed-use development in combination with some non-residential uses.*
- *Provide common usable or connected open space, parks, or plazas.*
- *Provide building height transitions and step-downs to be compatible with adjacent development.*

Staff Evaluation. ***Does not Comply.*** The portion of the PUD that is designated MUR is wholly commercial.

Mixed Use Employment Emphasis Designation.

The southwestern and northeastern portion of the PUD Site is designated **Mixed Use Employment**. The desired characteristics for that land use are as follows:

Create an environment that has employment opportunities integrating buildings and outdoor spaces transportation and parks, open space, civic uses, and other uses as appropriate.

- *Mix uses either vertically or horizontally.*
- *Develop in an integrated, pedestrian friendly manner and should not be overly dominated by any one land use.*
- *Provide building height transitions and step-downs to be compatible with adjacent development.*

Staff Evaluation: **Complies.** The PUD land use map designates two areas for commercial/non-residential development which would provide employment opportunities for City residents, for LCCC students, and for Sweetgrass residents who could walk to work. The PUD regulations contain specific design and development standards for this commercial development. The regulations do not specify a maximum amount or square footage for any one commercial land use or activity type. Rather, it appears to allow market forces to determine how much retail, office and service uses would develop within the two areas. However, the goal of the “village center” commercial node is to provide businesses that would serve LCCC students, faculty, other workers and visitors as well as residents of Sweetwater PUD. The goal of the Avenue C commercial center in the southwestern portion of the Site is to provide office and research space that would be more of a business center or employment campus as outlined in PlanCheyenne.

Rural Residential Designation.

The eastern portion of the PUD Site is designated for Rural Residential development. The PlanCheyenne desired characteristics for **Rural Residential** development are as follows:

Develop at densities lower than typically found in the more urban residential areas (e.g., within the Urban Service Boundary) with lifestyles oriented to more rural characteristics, such as keeping horses and other large animals, rather than convenience to services.

- *Roads may be paved based on the number of units and trips using the road.*
- *Landowners may develop large lot single-family rural residential, or cluster development on smaller lots to conserve open space, views, and other natural features.*

Staff Evaluation: ***Complies.*** The PUD land use map identifies large parcels for the low and very low densities characteristic of the Rural Residential land use designation. Those lots are oriented toward adjacent open spaces or the golf course. The PUD regulations would allow the clustering of lots in order to preserve natural topography, natural drainage systems or open spaces within the subdivision. Road types are proposed to be similar to the Neighborhood Street "A" type of the UDC, which would suffice.

4. The application reflects sound planning and urban design principles with respect to existing and potential future development in the vicinity, including consideration of current and future streets, open spaces, blocks and lots, and public utilities or facilities.

Staff Evaluation. ***Complies with a Condition.*** The Final Plan for the Sweetgrass PUD provides a land use map (Sheet 3 of Attachment A) that identifies areas for residential development of varying densities and non-residential development of varying intensities. It identifies lands for streets, schools, trails and open spaces. The large alphabet "Parcels" identified in the land use map would be further divided by developers of individual subdivisions or neighborhoods.

Sites for public utilities and community facilities, other than the City park and school sites, are not identified in the land use map. For example, a site for a fire station is not identified on the land use map. The PUD proposes a golf course which places a tremendous demand for irrigation water. The golf course would be an amenity for the Sweetgrass community providing recreation and open space. However, its irrigation water should not derive from the City's potable water supply but, rather, from the City's supply of treated effluent from the "purple pipes" or from recycled water from development within the Sweetgrass community. Low water use plant species should be used in all landscaping within the PUD Site, and particularly within the parks and golf course areas.

There is a 79-acre park tract that is proposed to be dedicated to the City; the size is based on preliminary discussions of the Applicant's representatives with City Parks and Recreation Department (Parks) staff. Based on the 5,000 dwelling units, it was estimated that the demand for a large Community park would be for about 68 acres. The 79-acre Community Park tract would be accepted for dedication to the City for development, ownership, operation and maintenance for PUD residents, workers and visitors as well as for members of the public.

The streets that front the Community Park should provide parking, including Avenue C which may be classified a minor arterial road. This parking is a valued asset to users of

the park both from within the Sweetgrass community and from City visitors and users. Appendix A, Sweetgrass PUD Street Sections, in Note 2, identifies Avenue C bordering the Site as a Minor Arterial which is to be improved per the UDC standards which does not allow parking along the street. Therefore, parking within the City park lands should be provided.

The revised Master Trails Plan, submitted on April 23, 2018, does not reflect the greenway route and alignment recommended by staff after review of the first submittal. Figure 6 below and Attachment C to this staff report shows the greenway route in green highlight with the exception of a segment abutting the Parcel B Village Center block which should be shorted to exclude the segment that begins at the proposed LCCC tunnel entrance and leads eastward to Sweetgrass Drive and then moves south to Murray Road because this segment is a redundant segment. The greenway route from the tunnel to the west to Goodnight Trail and then south to Murray Road is a more direct linkage to other greenway segments throughout the community. Lastly, due to the 12- to 15-foot change in elevation from where the tunnel exits under College Drive and the grade of the Sweetgrass land, the cost of building an ADA-compliant ramp to Sweetgrass Drive with safe slopes would be excessive for the Greenway Program's budget. Since it is costly and redundant, the City would seek to remove this segment from the Master Trails Plan Map as a City Greenway segment. This revision is recommended as Condition Number 1. Of course, the trail segment may remain as a private trail, but the City does not want it as a City dedication.




Figure 6 – Staff-recommended Greenway Route for the Master Trails Plan
Source: Landmark Engineering LTD

5. The application meets the purposes, intent, and all applicable standards in Article 4.

Staff Evaluation. **Complies.** The PUD regulation document incorporates by reference 43 standards of the UDC Article 4. Appendix C of the PUD Standards and Guidelines document lists those sections for the ease of project design of Applicants and of review of permitting staff.

Another reference in the PUD states that if the PUD regulations are "silent" on a particular development or design standard of a proposed development or permit application, the applicable UDC standard in effect at the time of the permit application would be applicable to measure the proposed development. For example, the PUD is "silent" on subdivision standards and processes; therefore the UDC Article 2 provisions for subdivisions in effect at the time of the application would apply.

6. ***Any phasing proposed in the application is clearly indicated and demonstrates a logical and well-planned development pattern. This may include consideration of amenities and public facilities of the subdivision within each phase compared to the anticipated timing or the likelihood of future phases being constructed as planned.***

Staff Evaluation. ***Complies:*** Sheet 5 of 6 of the PUD Maps (see Attachment A) includes a Phasing Plan. At this time, Sweetgrass is intended to be built out over 10 phases, with an assumed five years per phase. Page 3 of the Community Facilities Impact Assessment document shows some potential build-out rates for residential and non-residential land uses (see Attachment B). It is anticipated that the pace of development and sequencing will change over time due to market forces and the timing of infrastructure improvements beyond the Applicant's control. Therefore, updated Phasing Plans may be provided periodically for the purposes of coordination between the land owners, the City, and other interested parties. The timing of such revised Phasing Plans will be determined through the Annexation Agreement.

The Applicant may be the "master developer"; that is, the developer of the infrastructure needed to accommodate development of individual Parcels within the PUD. Whomever the master developer is, s/he is expected to build the initial infrastructure to serve each phase which would include extension of water and sewer lines, roads, traffic control devices, stormwater facilities, utilities and the like. The Annexation Agreement between the City and the Applicant outlines what public facilities and amenities would be developed, when they would be provided, and who would pay for those improvements.

-
7. ***The impacts identified in specific studies or technical reports that were prepared or requested to be prepared in association with the application, and whether the findings and recommendations of these reports, or any modifications or conditions on approval of the application, can mitigate these impacts.***

Staff Evaluation. ***Complies.*** The Applicant has submitted a transportation impact study (TIS) and a community facilities impact assessment of the proposed PUD development. These studies identify potential beneficial and adverse impacts of the PUD development to the City's public service resources and infrastructure and the City's ability to properly service the new community as well as existing communities within the area. The Annexation Agreement between the City and the Sweetgrass land owner(s) was informed by these impact assessments and incorporate measures to mitigate the impact and the fees to fund those improvements.

8. *The application is compatible with nearby property, specifically considering existing zoning, the Comprehensive Plan, and any other official plans and policies created under the guidance of that plan for these areas.*

Staff Evaluation. ***Complies.*** As noted above under Criterion 3, the proposed Sweetwater PUD is consistent with the PlanCheyenne future land use plan designations for this land which calls for urban residential densities for much of the PUD land. The Site is surrounded by County rural agricultural zoning designations. To the north lies the County PUD for the Laramie County Community College (LCCC) campus.

The PUD Site is currently devoted to grazing pasture lands for cattle associated with the Lummis family ranching operation. The surrounding neighborhood is characterized by mobile home parks, rural density residential lots, some business service and light industrial businesses, and numerous mini-storage operations. The northern edge of the Site is devoted to the Laramie County Community College (LCCC) campus and its numerous student services and activities.

The PUD would introduce neighborhood-serving and possibly regional-serving commercial uses to the neighborhood. However, the Lummis family ranch operation would continue with lands to the south and east of the PUD Site and the impacts of this new community on area street capacity and other City and County infrastructure is expected to be mitigated by expanded street construction and signalization as well as the extension of water, sewer and other utilities to the area.

If neighboring properties now lying within the County are annexed and served by City water and sewer lines, owners of those rural lots may seek higher density development. Should this be the case, staff would urge County property owners to join with their neighboring property owners to form a large, contiguous area for annexation in order to avoid County "pockets" surrounded by City properties.

9. *The suitability of the subject property for development according to the standards and uses of the existing zoning district, compared with the suitability of the subject property for development according to the standards and uses of proposed zoning district.*

Staff Evaluation. ***Complies.*** The proposed Sweetgrass PUD would introduce an entire community to former cattle ranch pasture lands. This land could be characterized as “raw land” suitable for such a new community because it has been annexed into the City and the City would provide essential public services such as water and sewer service, police, fire and emergency medical response services, parks and recreation services, street ownership, operation and maintenance services and the like. The new community proposed by the Sweetgrass PUD can be achieved under City jurisdiction principally because City water and sewer services can be extended to the land and to each lot within the PUD. In this way, the development would be suitable for this “raw land”.

10. The ability of the application to support the Intent and Applicability statements of the proposed zoning district, and achieve the Design Objectives of any specific standards.

Staff Evaluation. ***Complies.*** The PUD regulations document is “tailor-made” to the vision of the community the Applicants seek to establish on their land. The standards and regulations in the document support the Statement of Purpose in the document and would direct development of the lands to implement the Applicant’s vision for the land. The Applicant, Sweetgrass LLC, is actually a corporation made up of members of a ranching family, the Lummis family, that has lived and worked this land for generations. In public meetings, family members have articulated their desire that the Sweetgrass development results in an economically-viable, well-planned, well-designed and maintained and safe community that is an attractive asset to the land, to the nearby community, and to the City as a whole. The family has devoted several years to the planning and design of this PUD design and its regulations and believe a City PUD would be the best approach to implementing their vision and design objectives for the land.

The family intends to continue their ranching operation. The Statement of Purpose includes the following references to their ranching goals:

“A. Statement of Purpose

1. Sweetgrass is proposed as a ±2,349.5-acre community envisioned as a distinctive mixed-use master planned village, integrating retail, entertainment, lodging, employment opportunities, and variety of intimately scaled residential neighborhoods. All of these will be unified and connected through a comprehensive open space network with a variety of recreational amenities.
2. The Lummis family, historically cattle ranchers, have been good stewards of their land and ranching operations and are prepared to make the same commitment to the development of the Sweetgrass community.
3. The goals of the Sweetgrass Planned Unit Development (PUD) are as follows:
 - a. Create a community design that embraces the ranch's natural features, particularly its short grass prairie;
 - b. Promote a community vision committed to lifestyle and quality of life;

- c. Create smaller residential planning areas with a variety of residential products and density, creating a rich community texture and diversity, meeting the needs of students, singles, families, empty-nesters, and retirees;
- d. Develop an intimately scaled, pedestrian friendly Village Center that provides shopping and commercial development opportunities to complement the surrounding residential and employment communities, as well as serve as a focal point for the community;
- e. Incorporate a landmark golf course and destination resort and conference facility;
- f. Allow opportunities for the development of upscale commercial, retail, lodging, and entertainment venues along College Avenue;
- g. Provide a variety of recreational amenities;
- h. Incorporate an open space theme, focused on as many homes as possible being located on greenbelts or natural areas with a comprehensive hierarchy of pedestrian connections;
- i. Encourage the clustering of residential neighborhoods to reduce the impact of development;
- j. Incorporate community design principles to encourage sustainability and environmental stewardship; and,
- k. Enrich the residential, commercial and institutional resources of the City of Cheyenne and surrounding region. "

The PUD regulations also include the following standards for compatibility with ranching activity:

"I. Ranching / Agricultural Uses

- 1. The property to be developed as the Sweetgrass PUD is a working ranch.
- 2. Therefore, ranching and agricultural and activities and uses, and all accessory structures and uses which are customarily incidental or appropriate to farming and ranching, shall be permitted to continue on undeveloped lands throughout the Sweetgrass PUD prior to their development.
- 3. Public access to lands, including those lands planned to be dedicated to the City as open space, may be restricted prior to the construction of trails and other public amenities, the timing of which shall be determined through a Development Agreement with the City.
- 4. Prospective residents and/or buyers of homes or other properties within the PUD shall be made aware and shall acknowledge, in writing, that existing ranching operations should be expected to continue indefinitely on the ranch and properties nearby."

For these reasons, staff is of the opinion that the PUD standards and regulations will achieve the Applicant's Vision and design objectives for the land.

11. *The ability of all potential future development to meet all applicable standards for development in the proposed zoning district, including other development options in the event that any specific development proposed in association with the application is not executed after approval.*

Staff Evaluation. ***Complies.*** The PUD regulations incorporate residential and non-residential design and development standards which would guide development in each of the sub-areas or "Parcels" and "Tracts" of the PUD. Where the regulations are "silent", that is, not specifically addressed by the PUD regulations, the document states that "the must current

edition of the Cheyenne UDC shall govern". With this statement, any development proposal within the PUD district can be addressed by the PUD regulations or by the City's UDC regulations.

12. *Whether the planning and urban design concepts, and any proposed deviation from or alternative to otherwise applicable development standards, result in clear public benefits, as opposed to benefits to existing or future land owners in the development.*

Staff Evaluation. ***Complies.*** This criterion is positively addressed by the companion approved Sweetgrass PUD Annexation Master Annexation Agreement which is incorporated by reference in the Sweetgrass Final Planned Unit Development Standards and Guidelines document and by the Sweetgrass Traffic Impact Study (TIS) and Sweetgrass PUD Impact Assessment submittals required as part of the review criterion 7 and provided as part of the Final PUD application.

13. *The review and recommendations of other reviewing bodies.*

Staff Evaluation. ***Partially Complies.*** This criterion is partially addressed because many of the comments raised by City agency reviewers and the Wyoming Department of Transportation (WYDOT) reviewer have been addressed by the revised PUD regulations document and map exhibits. However, the eastern greenway segment from the tunnel to Sweetgrass Drive on the Master Trails Plan Map is recommended by the City's Community Recreation and Events Department to be removed as a greenway link due to costs of construction and its redundancy with the western segment. The Planning Commission recommended Condition Number 1 which would require that this segment be approved by the City or removed from the Master Trail Plan as a greenway segment.

14. *Whether the application will harm the public health, safety, or general welfare.*

Staff Evaluation. ***Complies.*** The PUD standards and guidelines are expected to guide development in a way that meets infrastructure needs as well as public service needs to Sweetgrass residents, workers and visitors. The Annexation Agreement identifies provisions for funding these improvements for internal development as well as improvements to mitigate any off-site impacts to the surrounding area associated with the Sweetgrass development.

15. The application is compatible with the character of the surrounding area in terms of building scale, building form, landscape, and site design.

Staff Evaluation. ***Complies.*** As noted above in review criterion Number 8, the PUD development would introduce a new and different type of development in an area surrounded by rural residential, higher density mobile home parks, a community college campus, business service and light industrial businesses, numerous mini-storage facilities, and a cattle ranch. The PUD development would resemble a master planned community or a suburban community in building scale, building form, landscape and site design, unlike the rural agriculture and rural residential character of the existing neighborhood.

However, one can state that the Laramie County Community College is a catalyst for the type of mixed-use development recommended by PlanCheyenne and proposed in the Sweetgrass PUD. The PUD would provide higher-density housing, perhaps student housing, in the northern portion of the PUD Site, along with commercial development of interest to students, workers and visitors to the college.

The PUD would also introduce a unique recreational and entertainment venue with a golf course and clubhouse/conference facility that can be of use by PUD residents as well as residents of the City as a whole. It is noted that the City's Board of Public Utilities (BOPU) is extending water and sewer mains to the PUD lands. Because of the tremendous demands upon the City's potable water supply by golf courses, the Applicant should bring treated effluent lines (the "purple pipes") to the golf course irrigation system. This use of treated effluent or recycled water rather than potable water should be provided to the PUD Site.

The PUD would also introduce a neighborhood-serving retail "village center" with businesses serving residents of the Sweetgrass community. There may also be retail and entertainment venues attracting a broader or regional patronage to the community.

The PUD would allow the continuation of cattle grazing on the PUD lands until such time as those lands are proposed for development. Therefore, there would be a transition from rural to urban densities and uses over the 50-year time period for full build-out of the PUD.

Because the 2,350-acre PUD land is in a single ownership, the Sweetgrass PUD land may be the best area to accommodate expected City population growth in a holistic manner, rather than with smaller, piecemeal developments or with splitting-off of 5-acre increment "ranchettes". Development within this planned community and with the Annexation Agreement between the City and the Applicant is expected to advance the most environmentally- and fiscally-sound approach to accommodating anticipated City growth over the 20 to 50 year build-out time period of this PUD.

This planned community, with public service financial stipulations outlined in the fully-executed Annexation Agreement, is expected to be a beneficial asset to the City and to the neighborhood.

CITY AGENCY COMMENTS ON SECOND SUBMITTAL:

MPO: Metro Planning Office (MPO), Nancy Olson

According to previous planning project Fox Farm Plan, there needs to be a Greenway (GW) along the East College Drive alignment that heads eastward. This could be accomplished by extending GW on Murray to where it intersects with Lummis. Also, the Sweetwater GW should extend to the future 4-legged intersection of College, College, Lummis and High Plains. The recently approved SE Greenway Trails connector plan shows a conceptual GW heading south along College to LCCC. Both these alignments were shown on past iterations of Sweetgrass Master Trail Plans.

Urban Planning: Richard Zita, Greenway Planner and Teresa Moore, Director of the City's Community Recreation & Events Department.

According to the Applicant's engineer, the eastern portion of the greenway connecting to the College Rd. tunnel from LCCC has a significant elevation change requiring steps. This does not meet ADA requirements and, therefore, cannot be included as a segment of the City's greenway trail. Therefore, the segment of trail on the final plat from the tunnel eastward to Sweetgrass Drive and south to Murray, if retained, must remain private and not greenway. [see Condition No. 1.]

OTHER COMMENTS: None on the second submittal.

Attachments:

- A. Sweetgrass PUD Regulations and Maps;
- B. Sweetgrass PUD Impact Assessment (Community Facilities Impact Assessment)
- C. Recommended Greenway Routes of the Sweetgrass PUD Master Trail Plan

C: Sweetgrass Ranch LLC--owner
Lee Martin, Landmark Engineering—agent for owner
UDC-18-00105 Project File



**Final
Planned Unit Development
Standards and Guidelines**

Printed: May 2, 2018

Prepared for:

Sweetgrass Land Co., LLC
c/o Mr. Doran E. Lummis
1825 Campstool Road
Cheyenne, Wyoming 82007

Landmark
Engineering
3521 W. Eisenhower Blvd.
Loveland, CO 80537
(970) 667 - 6286
Attn: Lee Martin, RLA
Project # SGRASS-1708-002



**This page intentionally left blank
for two-sided printing.**

Table of Contents

Section 1: General Provisions	Page 1
A. Statement of Purpose	Page 1
B. Application	Page 1
C. Maximum Density and Floor Area Ratio Standards	Page 2
D. Density Variations and Transfers	Page 2
E. Community Parks and Neighborhood Parks	Page 2
F. Underground Utility Requirements	Page 2
G. Ownership and Maintenance of Common Areas	Page 3
H. PUD Amendments	Page 3
I. Ranching / Agricultural Uses	Page 3
J. Temporary Uses	Page 3
K. Golf Course Routing and Safety	Page 3
L. Applications, Phasing, and Process	Page 4
M. Alternative Street Sections	Page 4
Section 2: Definitions	Page 5
Section 3: Development Standards & Guidelines	Page 7
A. Residential Parcels	Page 7
1. Applicability	Page 7
2. Street and Building Orientation around Neighborhood Parks and Schools	Page 7
3. Anti-Monotony Criteria	Page 8
4. Neighborhood Edges	Page 8
5. Exterior Materials	Page 8
6. Roof Design	Page 8
7. Front Porch Requirements	Page 9
8. Garages and Driveways	Page 9
9. Residential Lighting	Page 10
10. Internal Parks and Open Space	Page 10
11. Fences, Entry Monuments and Retaining Walls	Page 11
12. Common Recreational Vehicle Storage and Screening	Page 12
B. Non-Residential Parcels	Page 12
1. Applicability	Page 12
2. Landscape Design	Page 12
3. Lighting	Page 15
4. Signs and Entry Monuments	Page 17
5. Parking Requirements	Page 17
Section 4: Land Use Regulations	Page 19
A. Residential Parcels	Page 20
1. Intent	Page 20
2. Residential Building and Lot Standards	Page 20
3. Access to Residential Parcels	Page 20
4. Streets within Residential Parcels (check #'s below)	Page 20
5. VLDR – Very Low Density Residential	Page 20
6. LDR – Low Density Residential	Page 21
7. MDR – Medium Density Residential	Page 21
8. HDR – High Density Residential	Page 22
9. Single Family Attached and Multifamily Supplementary Design Standards	Page 22

B. Non-Residential Parcels	Page 25
1. Retail / Commercial	Page 25
2. Village Center	Page 26
3. Hospitality and Event Center	Page 26
4. Medical Office Campus	Page 27
5. Golf Course Clubhouse	Page 27
6. Office / Research Campus	Page 28
C. Park, School, and Open Space Tracts	Page 28
1. Community Park	Page 28
2. Schools	Page 28
3. Open Space	Page 29
Appendix A: Sweetgrass PUD Public Street Sections	Page A-1
Appendix B: Final Planned Unit Development Drawings	Page B-1
Appendix C: Cheyenne UDC Sections Incorporated by Reference	Page C-1

List of Tables

Table 1: Minimum Plant Quantities for Naturalized Landscapes	Page 14
Table 2: Recommended Plant Species for Naturalized Landscapes	Page 14
Table 3: Recommended Plant Species for Irrigated Landscapes	Page 15
Table 4: Residential Building and Lot Development Standards	Page 19
Table 5: High Density Residential SFA and MF Building	Page 20
Table 6: Landscape Design Standards for SFD Lots	Page 23
Table 7: Allowed Residential Land Uses by Category	Page 24
Table 8: Non-Residential Building and Lot Standards	Page 25
Table 9: Allowed Non-Residential Uses by Category	Page 30
Table 10: Sweetgrass PUD Roadway Design Information	Page A-1
Table 11: Roadway Technical Criteria	Page A-1
Table 12: Geometric & Urban Design Standards	Page A-2

List of Acronyms

CC&Rs	Codes, Covenants, and Restrictions
CMU	Concrete Masonry Unit
DU	Dwelling Unit
FAR	Floor Area Ratio
HOA	Home Owners' Association
LCCC	Laramie County Community College
LF	Lineal Feet
MF	Multifamily
PL	Property Line
PUD	Sweetgrass Planned Unit Development
ROW	Right of Way
SF	Square Feet
SFA	Single Family Attached
SFD	Single Family Detached
UDC	City of Cheyenne Unified Development Code

Section 1: General Provisions

A. Statement of Purpose

1. Sweetgrass is proposed as a ±2,349.5-acre community envisioned as a distinctive mixed-use master planned village, integrating retail, entertainment, lodging, employment opportunities, and variety of intimately scaled residential neighborhoods. All of these will be unified and connected through a comprehensive open space network with a variety of recreational amenities.
2. The Lummis family, historically cattle ranchers, have been good stewards of their land and ranching operations and are prepared to make the same commitment to the development of the Sweetgrass community.
3. The goals of the Sweetgrass Planned Unit Development (PUD) are as follows:
 - a. Create a community design that embraces the ranch's natural features, particularly its short grass prairie;
 - b. Promote a community vision committed to lifestyle and quality of life;
 - c. Create smaller residential planning areas with a variety of residential products and density, creating a rich community texture and diversity, meeting the needs of students, singles, families, empty-nesters, and retirees;
 - d. Develop an intimately scaled, pedestrian friendly Village Center that provides shopping and commercial development opportunities to complement the surrounding residential and employment communities, as well as serve as a focal point for the community;
 - e. Incorporate a landmark golf course and destination resort and conference facility;
 - f. Allow opportunities for the development of upscale commercial, retail, lodging, and entertainment venues along College Avenue;
 - g. Encourage a variety of recreational amenities;
 - h. Incorporate an open space theme, focused on as many homes as possible being located on greenbelts or natural areas with a comprehensive hierarchy of pedestrian connections;
 - i. Encourage the clustering of residential neighborhoods to reduce the impact of development;
 - j. Incorporate community design principles to encourage sustainability and environmental stewardship; and,
 - k. Enrich the residential, commercial and institutional resources of the City of Cheyenne and surrounding region.

B. Application

1. The regulations following in this PUD shall apply to all property contained within the "Sweetgrass Planned Unit Development," except as provided herein, and shall run with and bind all landowners of record, their successors, heirs, or assigns.
2. This PUD both references and diverges from the regulations contained in the Cheyenne Unified Development Code (UDC).
3. When the UDC is referenced herein, those sections of the UDC are shown in Appendix C to this PUD document.
4. Portions of the PUD are more stringent than the UDC; others are less stringent and/or provide a different approach. If the PUD does not address a specific item, the most current edition of the Cheyenne UDC shall govern; otherwise, this PUD shall govern.
5. The Sweetgrass PUD map sheets are exhibits that accompany this PUD, and are a part of these regulations.
6. Should any portion of this PUD be found to be invalid following its adoption, the remainder of the document shall continue to be in effect.

C. Maximum Density and Floor Area Ratio Standards

1. The maximum density permitted in any residential parcel and Floor Area Ratio in any non-residential parcel shall apply to the entire parcel and shall not be specifically applicable to any portion thereof.
2. The density of any residential parcel shall be computed by dividing the total number of dwelling units in the parcel by the gross acreage of the parcel.
3. The floor area ratio shall be computed by determining the gross footprint of the building, multiplied by number of stories (or any fraction thereof), divided by the gross acreage of the parcel.

D. Density Variations and Transfers

1. Density transfers are permitted without amending this PUD. In no event shall the total number of 5,000 residential dwelling units be exceeded.
2. Residential parcels may receive up to an additional ten percent (10%) of the maximum number of units allowed, as set forth in this PUD.
3. The total number of dwelling units actually developed in a Parcel may be less than the minimum established in this PUD.
4. Any decrease in units in a Parcel below the minimum identified in the PUD Master Plan may be transferred to other parcel(s) in whole or in part without amending this PUD.
5. An increase of dwelling units within a receiving parcel by more than 10% beyond the maximum described in the PUD may be accomplished through an Administrative Adjustment, as described in UDC Section 2.3.4, so long as the increase does not adversely affect the delivery of public services or substantially change the character of the PUD.

E. Community Parks and Neighborhood Parks

1. Based on the maximum number of units allowed in this PUD (5,000 units), to maintain the desired Level of Service of 5.8 acres of Community Parks per 1,000 residents (at 2.25 residents per unit), the Sweetgrass PUD is required to set aside a minimum of 67.2 acres of usable land.
2. Because much of the identity of Sweetgrass is based upon the golf course and wide open spaces, the location of the Community Park makes the most sense near the southeast corner of the intersection of College Drive and Avenue C.
3. The entire proposed dedication is within or immediately adjacent to the first phases of development, and will be easily accessible by the greatest number residents in Sweetgrass without creating a potential conflict with the golf course. The location is within 1.5 miles of more than 90% of the dwellings proposed in this PUD.
4. Because of the extensive open space network, the proposed golf course, the typical profile of those purchasing land adjacent to a golf course, the proximity of the proposed Community Park to the majority of future residents in Sweetgrass, and the large lots planned generally in the southern and eastern portions of Sweetgrass, private parks are not required within the Sweetgrass PUD. Nothing in this PUD is intended to prevent the developer of any individual parcel from creating a private park.

F. Underground Utility Requirements

1. All new electrical and communications distribution lines shall be placed underground.

G. Ownership and Maintenance of Common Areas

1. One or more homeowners associations, architectural review board(s), community development districts, and/or similar entities ("The Committee") shall be established to own, develop, improve, manage, and/or maintain common areas and amenities, as well as areas reserved for future development, throughout Sweetgrass following the adoption of this PUD.
2. Such common areas may include (but not be limited to) private parks and open space, the golf course and clubhouse, trails, private streets, common landscaped areas outside of publicly

maintained parks, and similar facilities. These common areas will exclude any lands dedicated or otherwise transferred to other entities, including school tracts and the Community Park.

3. The composition of the Committee, its roles and responsibilities, and other critical details, will be determined through the Conditions, Covenants and Restrictions (CC&R) document, or a state law governing community development districts.
4. The Committee reserves the right to prepare and enforce additional covenants, codes, and restrictions supplemental to this PUD, as well as act as a liaison between builders, other developers, and the City of Cheyenne as the Sweetgrass PUD develops.

H. PUD Amendments

1. From time to time, this PUD may require an amendment as conditions in the area evolve or other changes occur. The Committee is authorized to act on behalf of Sweetgrass owners and residents to petition the Director to make minor amendments to this PUD, subject to the procedures outlined in UDC Section 2.3.4 – Administrative Adjustment. Such amendments could include text amendments that do not affect materially the nature of the PUD, adjustments to parcel boundaries, changes to trail alignments, and/or other, similar items.
2. In the event that the Director finds that a proposed amendment is outside of the minor adjustments described within UDC Section 2.3.4.b.2, the Committee is authorized to act on behalf of Sweetgrass owners and residents to petition the Planning Commission for an amendment to this PUD pursuant to UDC Sec. 5.6.2.h.

I. Ranching / Agricultural Uses

1. The property to be developed as the Sweetgrass PUD is a working ranch.
2. Therefore, ranching and agricultural activities and uses, and all accessory structures and uses which are customarily incidental or appropriate to farming and ranching, shall be permitted to continue on undeveloped lands throughout the Sweetgrass PUD prior to their development.
3. Public access to lands, including those lands planned to be dedicated to the City as Community Park, may be restricted prior to the construction of trails and other public amenities, the timing of which shall be determined through a separate Annexation Agreement with the City.
4. Fencing adjacent to the Community Park shall not be barbed wire; smooth wire is acceptable.

J. Temporary Uses

1. Residential dwelling unit(s) may be utilized as model homes and/or sales and information offices within all residential parcels. The use shall be discontinued when all comparable dwelling units within the property have been sold or leased.
2. Mobile sales and information units may be utilized in any parcel, provided no such units are erected until a site plan for such has been approved by the City of Cheyenne.
3. Construction offices and material storage shall be permitted in all planning areas during, and for a period of ninety days after cessation of actual construction in these areas being served by such construction office or materials storage area.
4. The temporary uses permitted by City of Cheyenne as allowed with a "Temporary Use Permit" issued by the City of Cheyenne, pursuant to UDC Section 2.2.6.

K. Golf Course Routing and Safety

1. The golf routing in this PUD Land Use Plan is illustrative in nature and subject to change following the adoption of this PUD and recordation of final plat(s).
2. Every effort has been made to provide generous golf safety corridors to maximize the architect's flexibility and allow field adjustments to the ultimate course layout, specifically taking into account the high elevation, grade changes and prevalent wind conditions unique to the Sweetgrass PUD in southeastern Cheyenne, Wyoming.
3. Because of the flexibility with the golf routing described above and technological improvements, the golf course as it is ultimately constructed may change from that shown on the Final PUD.

Those purchasing property near the golf course shall acknowledge and accept the inherent risks associated with living in a golf community, which may include damages resulting from errant golf shots.

4. Recreational trails passing through the golf course, including trails that do not pass within golf safety zones, shall include prominent warning signs notifying users of the potential hazards of using the trail prior to entering the golf corridor.

L. Applications, Phasing, and Process

1. Following PUD adoption, the owners of PUD parcel(s) may submit site plans and/or plats for approval by the City of Cheyenne, as applicable. Such applications shall include a letter of endorsement from the Committee to be considered by the City. To receive a letter of endorsement, the applicant shall demonstrate to the satisfaction of the Committee that the applicant's plans and building concepts coincide with the goals and standards described within this PUD and the UDC, as applicable.
2. The PUD Map Exhibits include a Phasing Plan Exhibit. At this time, Sweetgrass is intended to be built out over eleven phases, with an assumed five years per phase; however, the pace of development and sequencing will almost certainly change due to market forces and the timing of infrastructure improvements beyond the Applicant's control. Therefore, updated Phasing Plans may be provided periodically for the purposes of coordination between the Committee, the City, and other interested parties. A change to phasing sequence will not trigger the need to amend this PUD.
3. An Annexation Agreement between the Committee and the City of Cheyenne outlining the timing of needed improvements, the construction phasing of those improvements and the complexity and the extent of those improvements shall be entered into prior to the approval of the first plat or permit application within the Sweetgrass PUD.

M. Alternative Street Sections

1. Because of the size of Sweetgrass, its rural character, and the goal of reducing public infrastructure and associated maintenance costs, alternative public street sections to the City's standard for collector and arterial streets (UDC §4.3) within and adjacent to Sweetgrass are a part of this PUD. Street sections allowed in Sweetgrass are illustrated in Appendix A of these Standards & Guidelines.
2. The Sweetgrass Street Sections may be adjusted slightly as construction plans are developed for special circumstances, such as roundabouts, accel or decel lanes, turning lanes, and/or other conditions, without amending this PUD and/or necessitating a formal Waiver to Subdivision Standards.

(End of Section)

Section 2: Definitions

A. Purpose

1. It is the purpose of this Article to define words, terms and phrases contained within this PUD Development Guide.
2. Refer to the current Cheyenne Unified Development Code for other definitions not defined herein.

B. Word Usage

1. In the interpretation of this Planned Unit Development, the provisions and rules of this section shall be observed and applied, except when the context requires otherwise. For definitions not found below, refer to Section 1.4 of the Cheyenne Unified Development Code; otherwise, the accepted dictionary definition in normal context shall apply.
2. The particular controls the general.
3. In the case of any difference of meaning or implication between the text of this document and any caption or table, the text shall control.
4. Words used or defined in one tense or form shall include other tenses and derivative forms.
5. Words in the singular number shall include the plural number and words in the plural number shall include the singular number.
6. The word "shall" is mandatory.
7. The word "may" is permissive.

C. Definitions

1. City: City of Cheyenne
2. Committee: Collective reference to any Homeowner's Association(s) and/or Architectural Review Committee(s) established to oversee development within Sweetgrass.
3. Community Park: Also referred to as "Tract 2." The approximately 70-acre tract of land at the southeast corner of Avenue C and Murray Road to be owned and maintained by the City of Cheyenne as a public park.
4. Director: Development Department Director, City of Cheyenne, or representative within the Development Department, as appropriate.
5. Dwelling Unit, Clustered: A type of single-family detached or attached dwelling unit development that combines reduced lot size with compensating amounts of open space within the proposed development.
6. Dwelling Unit, Patio Home: A single-family detached unit in which the private individual yard area associated with each dwelling unit is consolidated into a garden or patio area commonly located toward the side or rear of the lot. Generally each lot incorporates a use easement on the adjacent lot creating a larger side yard and/or rear corner patio and/or yard space, thereby increasing its outdoor living space. Maintenance of the exterior space is provided by a common entity, such as a homeowner's association or similar.
7. Dwelling Unit, Zero Lot Line: An alternative type of single-family detached dwelling unit which is situated on a lot so that one or more sides rest directly on the boundary line of the lot. Also referred to as a "Z-Lot" if the property line jogs. A use and/or maintenance easement is typically required on the adjacent lot for maintenance, drainage, and roof overhangs.
8. Dwelling Unit, Multifamily: For the purposes of this PUD, a multifamily dwelling unit shall be within a residential building comprised of 3 – 24 units, either for sale or rent.
9. Garage, Parallel (or Side-Facing): A garage, attached or detached, oriented such that vehicles entering the garage do so while substantially parallel to the street.
10. Garage, Perpendicular (or Front-Facing): A garage, attached or detached, oriented such that vehicles entering the garage do so while substantially perpendicular to the street.

11. Gross Acreage: The gross area of a parcel or tract, in acres, used for density calculations. The figure excludes collector street and arterial street rights of way (see "Parcel" and "Tract").
12. Open Space: For the purpose of this PUD, Open Space is defined as lands owned and maintained by the HOA or similar entity. Open space may include buffers, trails, golf courses, and other similar uses.
13. Parcel: For the purposes of this PUD, Parcels are real property to be platted exclusive of collector or arterial street right of way, intended to be developed for residential or non-residential uses as defined in Table 7 and Table 9, and are lettered from A through CC. Uses such as open space, parks and/or schools may be allowed in a Parcel, but are not the principal use of the Parcel (see "Tract").
14. Ranching Operations, Ongoing: For the purposes of this PUD, the existing ranching operations within the PUD that are planned to continue in undeveloped portions of the PUD as the property develops. Generally, these ranching operations include livestock grazing, haying, and maintenance (e.g., installation of barbed wire fences, etc.) related to the above allowed to continue following adoption of this PUD (See PUD Section 1.H).
15. Single Family Attached Lot: A fee-simple residential lot sharing at least one wall with an adjacent fee-simple residential lot.
16. Tract: For the purposes of this PUD, Tracts are real property to be platted exclusive of collector or arterial street right of way for open space, parks, utilities, schools, or other community facilities. Tracts are numbered from 1 through 13. Limited development may occur within Tracts, such as golf course maintenance, community park facilities, trails, utility conveyance, and other community facilities as defined in Table 9 (see "Parcel").

(End of Section)

Section 3: Development Standards & Guidelines

A. Residential Parcels

1. Applicability
 - a. The following standards apply to the principal structure and any accessory buildings, including detached garages, within residential parcels, or any portion of a parcel proposed to be developed as residential.
 - b. It is envisioned that builder(s) within each residential neighborhood within Sweetgrass will create a supplementary, more definitive set of Covenants and Design Guidelines specific to their respective development parcel or portion(s) thereof; however, any supplemental guidelines shall be within the parameters set forth below. A specific criteria established in this document may not be waived by a less stringent supplementary document without amending this PUD.
 - c. Additional standards and guidelines, so long as they are more restrictive, may be included within each Parcel.
2. Street and Building Orientation around Neighborhood Parks and Schools (Corresponding UDC requirement: N/A)
 - a. Intent: The goal of this section is to avoid the creation of "no-man's land" between residential lots and public spaces, particularly schools and neighborhood parks.
 - b. Schools:
 - i. To the maximum extent possible, the front and/or side façades of residential homes will face the school across public right of way ("Preferred", below)
 - ii. Under no circumstance shall a private property line be adjacent to a school without a minimum 50' width open space buffer separating the two ("Not Preferred," below)
 - iii. The buffer zone is to be owned, operated and maintained by the applicable HOA.




Figure 1: Neighborhood Layouts Adjacent to School (not to scale)

- c. Neighborhood Parks: A minimum of 50% of the neighborhood park perimeter shall be public right of way. Naturalized open space areas (e.g., trail corridors) are exempt from this requirement.

3. Anti-Monotony Criteria (Corresponding UDC Requirement: replaces UDC Section 6.6.3.b.2 - Model Variations)
 - a. Intent: Monotonous design of homes detracts from the quality of life in a neighborhood by lowering aesthetic and economic values and reducing pride of ownership. Therefore, all proposed models within each SFD neighborhood shall provide a minimum level of variability between front building elevations.
 - b. A minimum of four "distinctly different" home models shall be provided along each residential street with ten or more homes facing the street. In the event that fewer than ten homes are platted facing a street, only the remaining standards below shall be in effect.
 - c. The front elevation of each model must meet at least two of the following criteria to be considered "distinctly different":
 - i. Different number of stories;
 - ii. Different entry treatment and location, including porches, columns, etc.;
 - iii. Different façade composition consisting of different window / door style and placement, as well as different garage / entryway placement; and/or,
 - iv. Different roof form (slopes, lines, profiles, etc.).*(Note: changing roof colors and materials, changing paint color, adding a garage or garage bay, mirroring an elevation, etc., are not "distinctly different.")*
 - d. In no case shall a single family detached unit failing to meet the above criteria be built adjacent to or directly across the street from a similar model or elevation.
 - e. Enforcement: to be certified by the Committee prior to issuance of building permit. The Applicant shall provide a map and written statement from the Committee detailing conformance to this Section.
4. Neighborhood Edges (Corresponding UDC Requirement: N/A)
 - a. Intent: Neighborhood edges, which are highly visible from arterial and collector streets, parks, the golf course, and major trail corridors, shall maintain a high level of architectural character as seen from such adjacent public spaces.
 - b. Building elevations adjacent to neighborhood edges (including side and/or rear elevations, as applicable) must incorporate a minimum of 25% masonry (excluding windows and doors). Masonry shall wrap at least 2' on adjacent elevations for continuity.
5. Exterior Materials (Corresponding UDC Requirement: Supplements UDC Section 6.6.3.b.3)
 - a. Intent: Homes constructed within Sweetgrass are to be durable and of high quality.
 - b. Exterior materials may be natural wood, stucco, brick, or stone (including high quality faux brick / stone), in addition to lap siding. The Director may approve other materials if used creatively.
 - c. Lap siding, if used, shall have a maximum 6" exposed board face, and shall include at least a 25-year warranty.
 - d. Building colors should be subdued to blend with the colors of the natural landscape, although accent colors may be used with restraint. The use of highly chromatic, bright colors should be avoided, except in limited accent applications (e.g., doors and trim).
 - e. Exposed concrete blocks, painted concrete, unnaturally colored masonry, mirrored glass, prefabricated metal buildings, highly reflective materials, and unfinished aluminum door / window frames are prohibited.
6. Roof Design (Corresponding UDC Requirement: None)
 - a. Intent: Roof form and materials will be an important design element related to the character of residential neighborhoods in Sweetgrass, both internally from within Sweetgrass and its external edges. The goal of this section is to ensure a varied and appealing streetscape.
 - b. A roof pitch of 5:12 or greater shall be provided on all buildings.

- c. All roofs shall include a minimum 12" overhang.
 - d. Exceptions may be made at the Director's discretion for unique architectural designs or accents.
 - e. Quality roof materials shall be used on all buildings, to include tile, concrete tile, slate, architectural metal, dimensional composition, board & batten, or fiberglass shingles. Three-tab asphalt and cedar shake materials are not allowed.
 - f. Building roofs shall be broken into smaller planes or roof elements. A minimum of two roof breaks (roofs that turn a corner or change elevation) shall be provided on all homes. Large expanses of roof surfaces and long, uninterrupted ridge or eave lines shall be avoided. Dormers, cupolas, or other features shall be employed to mitigate roof lines exceeding 50 feet in length.
 - g. Mansard or large flat roofs are not permitted.
 - h. Rooftop mechanical equipment or ventilation pipes should be aggregated in a chimney stack with a screening canopy to the extent allowed by code, or placed out of view to the extent possible from public streets and major open space trails.
 - i. Exposed rooftop vents, flashing, sheet metal, etc., shall be painted with a color compatible with the underlying roof material. Exposed gutters and downspouts shall be designed as a continuous architectural feature and painted to match the adjacent roof or wall material.
 - j. Chimneys must be clad in the same brick or stone material as used on the front elevation of the building.
7. Front Porch Requirements (Corresponding UDC Requirement: Replaces UDC Section 6.6.4.b.1 - Entrance Features)
- a. Intent: To encourage social interaction between neighbors and passive surveillance of the public right of way, this section requires that a usable front porch be included with each single family detached home.
 - b. No single family detached home shall be constructed without a covered front porch as an integral part of the front elevation.
 - c. Front porches with a minimum area of 80 square feet and a minimum unobstructed depth of 6' shall be provided on each front elevation.
 - d. The porch may wrap to the side, particularly on corner lots.
 - e. Porch materials shall be the same as those used on the remainder of the structure, and be an integral part of its design.
8. Garages and Driveways (Corresponding UDC Section: Replaces UDC Section 6.6.4.a.4 - Front Loaded Garage Limits and Figure 6-7)
- a. Intent: Due to topographic constraints and the function of neighborhoods, particularly those neighborhoods adjacent to the golf course and open space network, front-loaded and/or side-loaded garages will be permitted on all SFD lots within Sweetgrass.
 - b. Garages may be attached to or detached from the principal structure.
 - c. One-, two-, and three-car garages are allowed on all SFD homes proposed in Sweetgrass, subject to the following:
 - i. If three-car garages are provided, the third space shall have a separate door with a minimum 2 foot separation horizontally behind the two-car garage door.
 - ii. A roof design change may be substituted for the horizontal separation in the third car garage.
 - iii. Windows must be incorporated into the design of each garage door.
 - iv. The garage door may not comprise more than 40% of the front elevation, excluding the roof.

- vi. Corner lots shall employ a side-loaded garage wherever possible, to be accessed via the side street (it is acknowledged that topographic constraints may not allow this to be enforced in every instance).
 - d. Driveway widths, measured at the curb of the public street (replaces residential lot portion of UDC Table 4-13):
 - i. Single-car garage: 10' or less
 - ii. Two-car garage: 18' or less
 - iii. Three-car garage: 27' or less
 - iv. In no event will the curb cut width exceed 27'.
 - v. Access widths are not determined by lot width.
 - e. Alley-loaded garage access is allowed in the MDR and encouraged in the HDR districts, although are not required in all instances (e.g., homes backing up to open space).
 - f. Driveway materials shall be limited to concrete. Concrete may be stamped or stained at the discretion of the homeowner.
9. Residential Lighting (Corresponding UDC Section: None)
- a. Intent: While it is acknowledged that lighting by homeowners on individual lots is required for safety and aesthetics, the preservation of night sky vistas is of paramount concern. Therefore:
 - i. All residential exterior lighting fixtures shall be fully cut off: no portion of the bulb is visible beyond two mounting heights from the fixture.
 - ii. No exterior light shall exceed 1,260 Lumens (measured on a per fixture basis).
 - iii. Barn lights, exposed bulbs, wall packs, and other lights intended to illuminate large areas are prohibited.
 - iv. Low-level architectural and landscape accent lighting are allowed, so long as the light source is not visible from adjacent properties.
 - v. Light levels shall not exceed 0.1 foot candles at 20' beyond an adjacent property line as a direct result of on-site lighting.
 - b. Seasonal lighting displays are allowed and are not subject to the above standards.
 - c. Nothing in this section is intended to preclude the installation of street lights in the public right of way by the utility company or in the Community Park.
10. Internal Parks and Open Space (Corresponding UDC Section: Replaces Section 4.4 - Open Space Systems)
- a. Open Space proposed within a residential parcel shall be:
 - i. Privately owned and maintained by an HOA or similar entity;
 - ii. Designed to be an integral feature of the residential parcel and major amenity and visible from neighborhood entry points, not "leftover space;"
 - iii. Platted as a tract (or tracts);
 - iv. Landscaped as a "Naturalized Landscape Area" as defined in Section 3.B.2.f of this PUD;
 - v. Varying in width to avoid long, straight fence runs;
 - vi. A minimum of 30'-in width, except for short distances if required (e.g., when connecting to a cul-de-sac bulb);
 - vii. Accessed via a recreational trail with a minimum 5' width;
 - viii. Connected on at least two locations to another trail and/or the public right of way (no dead end trails); and,
 - ix. Fenced adjacent to single-family detached lots per the detail in Section 11 – Fences and Retaining Walls below.
 - b. Parks provided within a residential parcel shall be:
 - i. Privately maintained;

- ii. Centrally located within the residential parcel or a linear park planned in conjunction with a regional trail corridor;
 - iii. Be adjacent to public right of way for at least 50% of the park boundary, unless otherwise approved by the Director;
 - iv. Planned to include amenities such as benches, drinking fountains, trash receptacles, play structures, hard- and/or soft-surface paths, playgrounds, turf practice fields, and/or other items to be determined on a case-by-case basis; and,
 - v. Landscaped as an "Irrigated Landscaped Area" as described in Section 3.B.2.f of this Section.
11. Fences, Entry Monuments and Retaining Walls (Corresponding UDC Section: Replaces UDC Section 5.8.4)
- a. Intent: Sweetgrass is intended to have an open feeling, borrowing heavily from surrounding open lands. An open style of fencing along open space areas contributes to this feeling.
 - b. Open rail wood fences, or metal picket fences may occur, and are not required, along College Drive, Avenue C, High Plains Road, Collector Streets, and the golf course. Any change in fence type (e.g., metal picket to open rail) shall occur at a masonry column.
 - c. Fencing along the above streets, if proposed, must be installed concurrently with the first phase of development in the adjacent residential parcel.
 - d. Privacy fencing is not allowed along the side of any residential lot adjacent to public parks, open space, or the public right of way.
 - e. Fences in areas of substantial grade change should be level and stair-stepped as required. Do not slope the top rail of any fence at greater than 5% (1 foot in 20 feet).
 - f. Fences along internal lot lines are not shown. Fences along internal lot lines shall match the open rail or privacy fence detail on Sheet 4 of the PUD Maps Exhibit.
 - g. Dog run fences are permitted within the building envelope (defined by the building setbacks) at least 5' behind the front façade of the home, as constructed. Plastic or vinyl fencing is not allowed for dog runs.
 - h. Double fences (constructing a privacy fence adjacent to an open rail fence to circumvent these regulations) are specifically not permitted.
 - i. Nothing in this PUD shall preclude the construction and/or maintenance of barbed wire or similar fences for the containment of livestock through ongoing ranching operations.
 - j. Entry Monuments and Retaining Walls
 - i. Entry monuments and retaining walls proposed in common open space areas must be approved by the Committee prior to City permitting.
 - ii. Materials shall be compatible with adjacent residential building materials or the Major Entry Monument Detail shown on Sheet 4 of this PUD. Wood, railroad ties, unfinished concrete, and CMU blocks are not permitted as finish materials.
 - iii. One entry monument per Residential Parcel is allowed per public street entry from a collector or arterial street.
 - iv. Illumination is restricted to back-lighting of letters or other obscured locations, and shall be low level.
 - v. Entry monuments may not exceed 12' height.
 - vi. Retaining walls exceeding 8' height will not be permitted without a terrace break and planter area at 3' width.
 - vii. Allowable materials include brick, stone, cultured stone, stucco, decorative CMU block, modular brick, or other similar materials not specifically mentioned if approved by the Director.
 - viii. Refer to Sheet 4 of the PUD Map Exhibit for Entry Monument Details. These details may be refined in future applications based on architectural themes to be developed.

12. Common Recreational Vehicle Storage and Screening (Corresponding UDC Section: None)
 - a. Intent: The unregulated long-term parking and storage of recreational vehicles in a neighborhood detracts from the quality of the neighborhood and its value, unless space exists for the above, and adequate mitigation is provided.
 - b. In certain instances in residential districts, the storage of a single recreational vehicle (e.g., motorhome, trailer, or boat) may be permitted, so long as the RV is operational, currently licensed and registered to the property owner, and adequately screened from the public right of way, adjacent open space tracts, adjacent parcels, and adjacent residential properties.
 - c. Screening shall consist of, at minimum, a Level 2 Screen, per UDC Table 6-11. If sufficient space for adequate screening does not exist on the lot, particularly as seen from trails within numbered Open Space tracts and arterial street right of way, the use shall not be approved in that location.
 - d. The storage or parking of a recreational vehicle in a public street, private street, driveway, or other location not permitted for a period exceeding 120 hours is prohibited.
 - e. This section does not preclude recreational vehicle storage within a garage or accessory building constructed to meet the standards of this PUD.

B. Non-Residential Parcels

1. Applicability
 - a. The following standards apply to:
 - i. Non-residential parcels;
 - ii. Portions of residential parcels to be developed as Multifamily and Single-Family Attached, including associated clubhouses;
 - iii. Portions of residential parcels to be developed with non-residential uses; and,
 - iv. Parks, Schools, and Open Space Tracts.
 - b. Developer(s) within applicable parcels will have the opportunity to create a supplementary, more definitive set of Covenants and Design Guidelines specific to their respective development parcel or portions thereof; however, those guidelines shall be within the parameters set forth below.
 - c. Additional standards and guidelines may be included within each non-residential land use designation.
 - d. A specific criteria established in this document may not be waived by a less stringent supplementary document without amending this PUD.
2. Landscape Design (Replaces UDC Section 6.3: Landscape Standards)
 - a. The quality and extent of landscape design in non-residential parcels will be of critical importance to the overall identity of Sweetgrass. The extent to which landscaping meets the standards described herein, while unifying the built portions of Sweetgrass, will be a major part of any Site Plan review.
 - b. Prior to any development application to the City, the developer shall submit a concept-level landscape plan to the Committee showing proposed landscape treatments in open space areas within the parcel, commonly maintained areas, and the public right of way within and adjacent to the development parcel to ensure substantial compliance, at a preliminary level, with the goals of this section.
 - c. Concept:
 - i. The Sweetgrass landscape concept is to establish a series of native and naturalized landscaped areas separated by a series of undisturbed (or restored) high plain prairie grasslands found on the site prior to its development.
 - ii. The naturalized landscape is to be an integral part of developed areas, providing a transition from developed to undeveloped land.

- iii. A variety of native and non-invasive naturalized trees and shrubs are to be used, and sited informally with the specific goal of minimizing the amount of irrigation water required.
- iv. Smooth grading and planting transitions will be essential to blending the built and undeveloped portions of the site, as well as for screening undesirable views and framing important vistas.
- v. To the maximum extent possible, trail corridors and drainages should be treated informally to emulate a more natural character.
- vi. The use of walls and abrupt grade transitions should be minimized, except as necessary to avoid grading in undisturbed grasslands adjacent to development parcels.
- d. Irrigation Requirements
 - i. All landscaped areas, with the exception of Native Areas, shall be irrigated with a permanent and automatic underground irrigation system to include soil moisture and rain detection devices with automatic shutoff switches.
 - ii. It shall be assumed for the purposes of irrigation design that recycled waste water will be available, or will become available, throughout the PUD. Therefore, irrigation systems will be designed to accommodate recycled water, even if not currently available.
- e. Undisturbed or Restored Native Landscapes
 - i. Intent: Nearly half of the Sweetgrass property is expected to remain as open, undeveloped grasslands, which are to remain undisturbed to the greatest extent possible. Aside from the golf course and trail corridors planned to meander through these areas, the existing native grasses are to remain in their current condition.
 - ii. Woody Plant Requirement: No minimum requirement.
 - iii. Recommended Plant Materials: Native grass mixtures as approved by the City of Cheyenne.
 - iv. Irrigation: No irrigation, save temporary systems for restoration of disturbed areas, is proposed. Temporary irrigation may consist of below- or above-ground systems, delivery via water truck, or other means.
 - v. Maintenance: Maintenance may include grazing, annual haying, controlled burns, manual removal of invasive species, and/or other means to promote the long-term health of the naturalized landscape.
- f. Naturalized Landscapes
 - i. Intent: Naturalized landscapes within Sweetgrass are intended to provide a transition between developed residential and non-residential parcels and undisturbed native landscapes. Landscape within naturalized areas should consist primarily of native grass restoration, with informal naturalistic groupings of native plant material in highly visible disturbed areas, particularly adjacent to major streets and along edges of narrow (i.e., less than 50' width) open space corridors.
 - ii. Woody Plant Requirement: The use of woody plant material in naturalized landscapes should be limited to:
 - (a) Tracts 2 and 3, as well as narrow (i.e., less than 200' across) trail corridors identified within Tracts 4, 8, 11, and 13; and,
 - (b) Disturbed areas adjacent to arterial streets, collector streets, and the golf course.
 - (c) Refer to Table 1 for Minimum Plant Quantities required, based on the width of the Naturalized Landscape.
 - (d) Refer to Table 2 for Recommended Plant Materials within Naturalized Landscapes.

Table 1: Minimum Plant Quantities for Naturalized Landscapes

Open Space Width	Minimum Plant Material Required
< 50'	1 Tree + 10 Shrubs per 200 LF of trail
50' to <100'	1 Tree + 10 Shrubs per 500 LF of trail
100' to <200'	1 Tree + 5 Shrubs per 1,000 LF of trail
≥ 200'	No minimum requirement
Notes: 1. At least 50% of trees shall be evergreen (4' ht at planting). 2. Deciduous trees shall be #15 container size minimum (canopy) and #10 container minimum (understory). 3. Shrubs shall be #2 container size minimum. 4. One tree may be substituted for ten shrubs, and vice versa. 5. No minimum plant material is required for trail corridors adjacent to the south and east project boundaries. 6. Clustering of plant material, particularly near public right of way, is encouraged.	

Table 2: Recommended Plant Species for Naturalized Landscapes

Recommended Tree Species	
<i>Juniperus scopulorum</i>	Rocky Mountain Juniper
<i>Pinus edulis</i>	Piñon Pine
<i>Pinus ponderosa</i>	Ponderosa Pine
Recommended Shrub Species	
<i>Acer grandidentatum</i>	Big-tooth Maple
<i>Amelanchier spp.</i>	Serviceberry
<i>Artemisia spp.</i>	Sage, Tall Western Sage, etc.
<i>Atriplex spp.</i>	Saltbush
<i>Cercocarpus spp.</i>	Mountain Mahogany
<i>Chrysothamnus spp.</i>	Rabbitbrush
<i>Juniperus spp.</i>	Juniper species
<i>Prunus americana</i>	American Plum
<i>Prunus besseyi</i>	Western Sand Cherry
<i>Quercus gambellii</i>	Gambel's Oak
<i>Rhus trilobata</i>	Three-leaf Sumac
<i>Rhus glabra cismontana</i>	Rocky Mountain Sumac
<i>Ribes spp.</i>	Native Currants
<i>Rosa woodsii</i>	Wood's Rose
<i>Shepherdia spp.</i>	Buffaloberry
<i>Yucca glauca</i>	Soapweed
Groundcovers: Northern Plains Native Grass Mixture by Applewood Seed Company or approved equal (contains Blue Wildrye, Slender Wheatgrass, Blue Grama, Little Bluestem, Indian Ricegrass, Sandberg Bluegrass, Prairie Junegrass, Green Needlegrass and Needle-and-Thread).	

- iii. Irrigation & Maintenance
 - (a) Irrigation is limited to the establishment of new material for two - three growing seasons.
 - (b) Irrigation may consist of a temporary above- or below-ground system, water truck, or delivery by other temporary means.
 - (c) Maintenance may include grazing, annual haying, controlled burns, manual removal of invasive species, and/or other means to promote the long-term health of the naturalized landscape.
- g. Irrigated Landscapes
 - i. Intent: Irrigated landscapes include areas within developed residential and non-residential parcels, schools, office campuses, streetscapes, and areas actively used for recreation. Ornamental plants within these areas should be hardy and drought-tolerant species proven to be non-invasive, with irrigated turf grass areas limited to active use areas, athletic fields, or similar. Planting arrangements may be formal or informal.
 - ii. Minimum Plant Materials Required:
 - (a) Trees: per UDC Section 6.3 Tree Points, Table 6-8.
 - (b) Shrubs & Groundcovers: per UDC Section per UDC Section 6.3, Table 6-9, except that points shall be awarded for only shrubs, flowering perennials, and ornamental grasses.
 - iii. Recommended tree and shrub species: All tree and shrub species identified in Naturalized Areas (above) and those identified in Table 3 (below).

Table 3: Recommended Plant Species for Irrigated Landscapes

Recommended Tree Species	
<i>Acer tataricum</i>	Tatarian Maple
<i>Acer negundo</i> 'Sensation'	Sensation Maple (Male clone that does not attract boxelder bugs)
<i>Celtis occidentalis</i>	Hackberry
<i>Crataegus ambigua</i>	Russian Hawthorn
<i>Gymnocladus dioica</i>	Kentucky Coffeetree
<i>Malus spp.</i>	Crabapple (Fireblight resistant varieties only)
<i>Pinus nigra</i>	Austrian Pine
<i>Quercus macrocarpa</i>	Burr Oak
(Other tree species may be proposed, so long as they are drought tolerant, disease resistant, and suitable for the climate in Cheyenne.)	
Recommended shrub species: All shrub species identified in Naturalized Landscapes (above), plus additional shrubs to be approved on a case-by-case basis, so long as they have been identified as being moderately water consumptive or less.	

- iv. Irrigation & Maintenance: per UDC Sections 6.3.7 and 6.3.8, unless modified below.
- 3. Lighting (Replaces UDC Section 6.4: External Lighting)
 - a. Intent: Preservation of night sky vistas is of paramount concern to Sweetgrass, particularly in residential neighborhoods.
 - i. Except as otherwise noted, all light fixtures are required to be full cutoff as defined by the Illuminating Engineers Society of North America. Full cutoff light fixtures result in a light

- distribution pattern where no light is permitted at or above a horizontal plane at the bottom of the fixture.
- ii. No portion of the bulb or direct lamp image may be visible beyond two mounting heights from the fixture.
- iii. Light levels shall not exceed 0.1 foot candles at 20' beyond an adjacent property line as a direct result of on-site lighting.
- iv. Lamps shall not exceed 900 lumens for any single lamp.
- v. Beacons, search lights, blinking, flashing, or changing intensity lights are prohibited, except for temporary holiday displays.
- vi. No outdoor lighting may be used in any manner that could interfere with the safe movement of motor vehicles on public thoroughfares.
- vii. The use of warm temperatures is encouraged throughout Sweetgrass. For fixtures installed outside of the public right of way, light temperature may exceed 3,000 K if such fixtures are shielded, such that spillover light does not encroach within residential neighborhoods or open space areas.
- b. Sports Fields and Parks
 - i. Sports field lighting is allowed for public parks and outdoor gathering spaces greater than ten acres.
 - ii. All exterior sports field lights used for the purpose of illuminating a playing area must be extinguished by midnight or immediately following the conclusion of the final event.
 - iii. The remainder of facility lighting, except for security lighting, must be extinguished at midnight or within one hour following the event.
 - iv. For security, a maximum level of 1.5 foot-candles at entrances and stairways, and 0.5 foot-candles on the rest of the site is permitted.
- c. Building and Security Lighting
 - i. Non-shielded industrial-type building-mounted floodlights, such as wall-packs, are not permitted.
 - ii. Low-level building-mounted lighting, shielded via architectural sconces, may be used in some situations, although may not be used to illuminate large exterior ground-level areas.
 - iii. Any special security lighting shall be confined to building entries or outdoor pedestrian areas.
 - iv. With the exception of low-intensity fixtures, the lighting source shall not be visible from the public right of way.
- d. Building Façade Illumination
 - i. Illumination of a building façade to enhance architectural features may be permitted if approved on a Site Plan, and not intended to advertise or exhibit buildings or properties.
 - ii. Downlighting is preferred, provided that wall-mounted fixtures are used and illumination is contained completely within the vertical face of the building and does not spill off the building edge.
 - iii. Uplighting may be permitted, providing that no illumination escapes the façade.
 - iv. Building façades may be illuminated to a maximum of 20 foot-candles as measured at any point on the façade.
 - v. Lights mounted on poles for the purpose of illuminating a building façade will not be permitted.
 - vi. All illumination sources must be located within the property boundary and be shielded from public view so that light is controlled within the area to be illuminated.
 - vii. Lamp selection should ensure that the source color is compatible with the building color and theme.

- e. Poles
 - i. The style of light poles must be compatible architecturally with the building design. Poles and luminaires must be uniform in color, anodized or painted to be compatible with the building color theme.
 - ii. Athletic field lighting shall adhere to current National Standards for that type of facility.
 - iii. Poles should be placed in landscape areas whenever possible (vs. parking lot pavement and sidewalks).
 - iv. Poles located adjacent to parking shall be located a minimum of 2.5' back from the face of curb, as measured from the nearest edge of the base.
 - v. Unfinished concrete pole bases may not extend more than 6" above surrounding grade.
 - f. Service and Storage Areas
 - i. Service area lighting shall be contained within the service yard boundaries and enclosure walls.
 - ii. No light spillover can occur outside the service or storage area.
 - iii. The lighting source shall not be visible from the public right of way.
 - g. Landscape and Pedestrian Areas
 - i. Accent lighting of landscape elements is permitted, provided that the lighting is low-level, background in appearance, and uses a concealed source.
 - ii. Colored accent lighting is not permitted (with the exception of seasonal displays).
 - iii. Lighted pedestrian walk and exterior paved areas adjacent to buildings must use low-intensity fixtures, with light color compatible with surrounding area lighting.
4. Signs, Fences, and Entry Monuments (Supplements UDC Section 6.5: Signs)
- a. UDC Section 6.5 (Signs) shall govern, unless superseded by an approved detailed sign program for the entire PUD and/or specific parcels therein following adoption of this PUD.
 - b. Entry monuments will be permitted at entrances to commercial parcels and residential neighborhoods. As these are intended to be design elements that unify the overall Sweetgrass PUD and not advertise specific private businesses, entry monuments will not count toward the sign face area as defined in the UDC.
 - c. Materials shall be compatible with adjacent building materials or the Major Entry Monument Detail shown on Sheet 4 of this PUD Map Exhibit. Wood, railroad ties, and unfinished concrete are not permitted as finish materials.
 - d. Except for entry monuments within 700 feet of College Drive, illumination is restricted to back-lighting of letters or other obscured locations, and shall be low level.
 - e. Additional fences and walls within non-residential parcels and tracts, including the golf course clubhouse, conforming to the details on Sheet 4 of the PUD Map Exhibit or similar materials and methods may be approved by the Director for a valid purpose, such as promoting an urban design theme, controlling pedestrian traffic, defining an outdoor seating area, screening undesirable elements, etc.
 - f. A privacy fence matching the detail shown on PUD Map Exhibit Sheet 4 of 4 may be constructed adjacent to the golf course maintenance facility, including adjacent to public right of way.
5. Parking Requirements (Supplements UDC Section 6.2: Parking, Lot Access and Circulation)
- a. Parking shall comply with the standards in UDC Section 6.2.
 - b. Parking setbacks specific to this PUD are in Table 8 of this PUD.

(End of Section)

This page intentionally left blank
for two-sided printing.

Section 4: Land Use Regulations

Table 4: Residential Building and Lot Development Standards Summary

District	Building Setbacks by Lot Product Type				Minimum Building Separation	Maximum Building Height	Minimum Lot Size	Maximum Accessory Building Size	Density Range
VLDR	Front Yard		25'		16'		15,000 SF	1,500 SF	0.1-2 DU/Ac
	Side Yard - Internal / ROW		15'/25'						
	Rear Yard		15'						
LDR	Front Loaded SFD	Front Yard	15'		10'	35'	7,000 SF	1,200 SF	2-4 DU/Ac
		Front Facing Garage	20'						
		Side - Internal / ROW	8'/20'						
		Rear	15'						
	Cluster / Zero Lot Line SFD	Front Yard	10'		10'		5,500 SF	N/A	
		Front-Facing Garage	18'						
		Side - Internal / ROW	0'/10'						
		Rear	15'						
	Patio SFD	Front Yard	8'		10'		5,500 SF	N/A	
		Front Facing Garage	18'						
		Side - Internal / ROW	7.5'/15'						
		Rear	15'						
MDR	Front / Alley Load SFD	Front Yard	10'		10'	35'	5,000 SF	600 SF	4-10 DU/Ac
		Front-Facing Garage	20'						
		Side - Internal / ROW	7.5'/15'						
		PL to Alley (w/ Parking)	20'						
		PL to Alley (w/o Parking)	4'						
	Cluster / Zero Lot Line Setbacks: Same as LDR Cluster						4,500 SF	N/A	
	Patio SFD Setbacks: Same as LRD SFD								
HDR	Alley-Loaded SFD Setbacks: Per MDR Alley-Loaded SFD					35'	4,000 SF	600 SF	10-24 DU/Ac
	Duplex & Single Family Attached	Front Yard	15'		Minimum Building Separation Varies by no. Of Stories (Table 5)	45' by Right; 60' by Administrative Review	Duplex Unit: 3,500 SF	600 SF	
		Side — Internal / ROW	7.5'/15'				SFA Unit: 2,200 SF	N/A	
		Bldg. to Alley (w/ Parking)	18'				No Minimum	Detached garages and carports are allowed and are not considered accessory structures in this context.	
		Bldg. to Alley (w/o Parking)	4'						
	Multifamily	Bldg. to Local St. ROW	25'						
		Bldg. to Collector St. ROW	30'						
		Bldg. to Property Line	30'						
		Bldg. to Parking	4'						
		Garage to Private Drive w/o Parking	3'						
	Garage to Private Drive w/ Parking	20'							
	Non-Residential Uses Allowed in HDR District: Standards in Village Center Land Use (Table 8) Apply								
Notes:									
1. Accessory Buildings: One accessory building is allowed in each single-family detached lot. None are allowed on lots with cluster homes, zero lot line homes, and patio homes. The accessory building shall be set back at least 10' behind the front of the principal structure, as constructed. The side and rear yard setbacks described above also apply to accessory buildings and detached garages.									
2. Encroachments for architectural features, such as chimneys and bay windows, of up to and including 2.5' within side yard setbacks are allowed, such that a minimum of 10' clear between building walls is maintained.									
3. Distance measurements are in feet unless otherwise noted.									

Table 5: High Density Residential SFA and MF Building Setbacks Standards

SFA / MF Building Orientation	1-Story	2-Story	3-Story and Greater	Note: The minimum separation between buildings of varying heights is determined by the taller of the two buildings.
Building Front to Building Front	20'	25'	30'	
Building Side to Building Side	10'	15'	20'	
Building Side to Building Front (or Back)	20'	25'	25'	
Building Back to Building Back	30'	40'	40'	

A. Residential Parcels

1. **Intent:** The following residential standards are intended to facilitate the orderly development of residential lands within the Sweetgrass PUD in a manner unique to Southeastern Wyoming.
2. **Residential Building and Lot Standards:** Setbacks, Minimum Lot Sizes, Building Separations, Maximum Building Height, Maximum Accessory Building Size, and Maximum Gross Density: Per Table 4.
3. **Access to Residential Parcels:** Because Sweetgrass is a series of neighborhoods designed within a planned collector street network around a significant open space system, the access guidelines contained within UDC §4.3.3.f.3(a) – (d) are not applicable. Residential development parcels shall provide access sufficient for emergency vehicles (per International Fire Code, as adopted by the City when the final plat for the residential parcel is submitted), with a minimum Level of Service of "C."
4. **Streets within Residential Parcels**
 - a. **SFD Residential Neighborhoods:** Streets shall be dedicated public right of way per UDC "Standard Roadway: Residential."
 - b. **Non-SFD Residential Neighborhoods:** Streets and drives providing access to internal parking and garages, including alleys, may be privately owned and maintained.
 - c. Any alleys proposed will be constructed to Context-based Roadway: Alley.
 - d. A parcel, or a portion of a parcel, within the district may be gated, subject to the approval of the Cheyenne Fire Department.
 - e. Any gated streets will be privately maintained.
 - f. Alternative street sections may be approved with concurrence by the City Engineer and Fire Chief following the adoption of this PUD.
5. **VLDR – Very Low Density Residential**
 - a. **Intent:** The Very Low Density Residential land use categories are located generally east of High Plains Road to transition from greater intensity to less intensity, with generous swaths of native and naturalized open space areas internal to each parcel. Residential uses allow for large lot estate SFD homes, custom SFD homes, and semi-custom SFD homes. Portion(s) of VLDR neighborhoods may be gated.
 - b. **Permitted Uses:** Per Table 7.
 - c. **Streets:**
 - i. Streets shall be dedicated public right of way per UDC Standard Roadway: Residential, with the exception of subsection iv below.
 - ii. A parcel, or a portion of a parcel, within the district may be gated, subject to the approval of the Cheyenne Fire Department.
 - iii. Any gated streets will be privately maintained.
 - iv. Alternative street sections may be approved by the Committee with the concurrence of the City Engineer and Fire Chief for private streets following the adoption of this PUD.
 - d. **Private Parks and Open Space**
 - i. Private Parks are not required.
 - ii. At least 90% of platted lots within an LDR parcel shall abut private open space with a minimum of 50' width.

- e. **Supplementary Design Standards (In addition to Section 3.C above)**
 - i. Ranch style (single story) homes are strongly encouraged. Should a second story be desired, no more than half of the building footprint (including the garage) may be used for the second story.
 - ii. Parallel garages, or garages set at least 20' behind the front façade, are required on all homes proposed within 30' of the front lot line.
 - iii. Landscape Design on Individual Lots: per Table 6 below.
- 6. LDR – Low Density Residential**
- a. **Intent:** The Residential-Low Density land use category is intended to provide for residential development allowing for a variety of single-family detached dwelling units, including but not limited to traditional single-family homes, zero lot line dwelling units, clustered single-family dwelling units and accessory uses. Generous open space areas should be provided internal to each LDR parcel.
 - b. **Permitted Uses:** Per Table 7.
 - c. **Clustering Incentive:** If 50% or more of a LDR parcel is platted open space with all units abutting the open space, the following incentives shall apply to allow Cluster Homes, Zero Lot Line Homes, and Patio Homes:
 - i. Minimum lot size may be reduced to 5,500 SF;
 - ii. Side yard setbacks may be reduced to 0', so long as a 10' building separation is maintained; and,
 - iii. Rear yard setbacks may be reduced to 10'.
 - d. **Private Parks and Open Space**
 - i. Private parks are not required.
 - ii. At least 75% of platted lots within a parcel shall abut to open space with a minimum of 75' width.
 - e. **Supplementary Design Standards (In addition to Section 3.C above)**
 - i. At least 30% of the front elevation (excluding windows and doors) shall be masonry. Masonry shall wrap at least 2' on adjacent elevations for continuity.
 - ii. Landscape Design on Individual Lots: per Table 6.
- 7. MDR – Medium Density Residential**
- a. **Intent:** The MDR land use category is intended to provide for residential development allowing for a variety of single-family detached and attached dwelling units, located nearby to schools and commercial centers. An extensive open space network should be provided within each MDR parcel. To promote greater diversity, lower density development, such as that permitted within LDR districts, is permitted within MDR districts.
 - b. **Setbacks, Minimum Lot Sizes, Building Separations, Maximum Building Height, Maximum Accessory Building Size, and Maximum Gross Density:** Per Table 4.
 - c. **Permitted Uses:** Per Table 7.
 - d. **Clustering Incentive:** If 50% or more of a MDR parcel is platted open space with all units abutting the open space, the following incentives shall apply to allow Cluster Homes, Zero Lot Line Homes, and Patio Homes:
 - i. Minimum lot size may be reduced to 4,500 SF;
 - ii. Side yard setbacks may be reduced to 0', so long as a 10' building separation is maintained; and,
 - iii. Rear yard setbacks may be reduced to 10'.
 - f. **Private Parks and Open Space**
 - i. Private parks are not required.
 - ii. At least 80% of platted SFD lots within a parcel shall abut open space with a minimum of 40' width.

- g. Single-Family Detached Residential Supplementary Design Standards (in addition to Section 3.C above).
 - i. At least 35% of the front elevation (excluding windows and doors) shall be masonry. Masonry shall wrap at least 2' on adjacent elevations for continuity.
 - ii. Landscape Design on Individual SFD lots: per Table 6.
- 8. HDR – High Density Residential
 - a. Intent: The HDR - High Density Residential land use category is located in close proximity to Laramie County Community College and planned retail / commercial development along College Drive. These parcels are intended to provide for residential development to support the student and employee housing needs associated with the community college and surrounding community in the form of apartments, townhomes, and more affordable single family detached dwellings. To promote greater diversity, lower density development, such as that permitted within MDR and LDR districts, is permitted within HDR districts.
 - b. Setbacks, Minimum Lot Sizes, Building Separations, Maximum Building Height, Maximum Accessory Building Size, and Maximum Gross Density: Per Table 4.
 - c. Permitted Uses: Per Table 7.
 - d. Private Parks and Open Space
 - i. Unless exempted per §3 A.10.b of these Standards, private parks are required at the rate of 0.025 acres per unit within a parcel, either in land or in fee, through the first hundred units. No additional park dedication is required in that parcel. (Patio Homes and Cluster Homes are exempt from this requirement).
 - ii. At least 60% of platted SFD lots within any HDR parcel shall abut to open space with a minimum of 30' width.
 - e. Single Family Detached Residential Supplementary Design Standards (in addition to PUD Section 3.C above): per SFD Residential Supplementary Design Standards in MDR.
- 9. Single-Family Attached and Multifamily Residential Supplementary Design Standards
 - a. Site Design
 - i. The front elevation of each unit shall face either the public ROW, a private drive, or open space (internal to the parcel or as a numbered Tract in the PUD).
 - ii. Garage access shall be from a private drive.
 - iii. At least one third of all parking provided shall be within garages (applicable to SFA only). The remainder of parking requirements shall be per UDC Section 6.2.
 - iv. Both attached and detached garages are allowed. Should detached garages be provided, no more than six vehicle spaces shall be constructed in the same garage structure. Detached garage structures shall have a 10 foot building separation.
 - v. For any SFA / Multifamily neighborhood with more than 100 units, the following will be required:
 - (a) A clubhouse of at least 1,000 SF area; and,
 - (b) A centrally-located landscaped common area of at least 1.0 acre, with age-appropriate play equipment, hard-surface sport courts (i.e., tennis, basketball, etc.), open turf play areas, and/or other amenities to be approved by the Director on a case-by-case basis (landscape and hardscape areas, including the clubhouse area, may be credited to the private park area).
 - vi. Gated communities may be allowed.
 - vii. A covered and lighted structure will be provided over mailbox units, and will match or complement the building architecture.
 - b. Architectural Design
 - i. SFA Buildings shall include no more than eight units in a single building.
 - ii. MF Buildings shall include no more than twenty-four units in a single building.

- iii. Architectural detailing, horizontal offsets, architectural window details, and other features shall be provided to avoid blank walls.
- iv. All sides of all SFA buildings shall be designed with high-quality materials, as described within UDC Table 6-18 and UDC Section 6.6.3.b.3 (Materials for Multifamily Buildings).
- v. A specific criteria established in this document may not be waived by a less stringent supplementary document without amending this PUD.
- c. Landscape Design: per Section 3.B.2.f (Irrigated Landscape) of this PUD. SFD lots shall be landscaped per Table 6.

Table 6: Landscape Design Standards for SFD Lots

Intent:			
1. Minimize water use in private landscapes by limiting turf to the highest use areas;			
2. Visually soften the appearance of architecture in the front yard by ensuring that a minimum quantity of trees and shrubs are provided.			
Land Use Category	Front Yard Landscape	Side & Rear Yard Landscape	Maximum Area of Irrigated Turf Grass
VLDR	1 Tree + 10 Shrubs / 2000 SF	None required.	25% of Landscaped Area
LDR	1 Tree + 5 Shrubs / 1000 SF		30% of Landscaped Area
MDR & HDR	1 Tree + 3 Shrubs / 1000 SF		40% of Landscaped Area
Notes:			
1. Front Yard Landscaped Area is defined as unpaved areas between the front façade and right of way.			
2. Trees within the public right of way may count toward the above requirements.			
3. Round fractions of plants up or down to the nearest whole number (0.5 becomes 1).			
4. One tree may be substituted for 10 shrubs or 15 ornamental grasses, or vice versa.			
5. Minimum Planting Size: Canopy Trees - 1" Caliper; Ornamental Trees – 15 gallon container; Evergreen Trees – 4' height; Shrubs – 1 gallon container; Ornamental Grasses – 1 gallon container.			

Table 7: Allowed Residential Land Uses by Category

Proposed Land Use		Residential Land Use Categories			
		VLDR	LDR	MDR	HDR
Residential Land Uses	Single-Family Detached Residential (see Note 2 below)	P	P	P	P
	Cluster & Zero Lot Line SFD Residential		P	P	P
	Patio SFD Homes		P	P	P
	Single-Family Attached Homes (Duplexes and Townhomes)		P	P	P
	Single-Family Attached Homes (Duplexes and Townhomes)		P	P	P
	Multifamily Homes (Apartments and Condominiums)			P	P
	Mixed-Use Dwelling				A
	Accessory Dwelling Unit	A	A		
	Accessory Structure	P	P	P	P
	Home Occupation	P	P	P	P
	Live-Work (per UDC 5.7.7)				P
	Personal Recreational Vehicle Storage (on Lots 15,000 SF and greater)	A	A		
Non-Residential Uses	Stormwater Detention Ponds, including Regional Ponds	P	P	P	P
	Utility Conveyance	P	P	P	P
	Public and Private Parks and Open Space	P	P	P	P
	Community Athletic Field	P	P	P	P
	Neighborhood Assembly (up to 350 person capacity): church or clubhouse	A	A	P	P
	Government Facility, such as a Fire Station, Police Substation, or similar		A	P	P
	Adult Care, Assisted Living				A
	Child Care, in Home – Minor		P	P	P
	Child Care, in Home – Major			A	A
	Child Care, Center – Minor			A	A
	Child Care, Center – Major				A
	Utility Stations, such as water wells, pump stations, and similar facilities (not offices or storage yards)	A	A	A	A
	All Permitted Uses by Right in the Village Center Category of this PUD, on up to 15% of the Gross Land Area (see note 4 below)				A
Legend: P Use Permitted by Right A Use Permitted by Administrative Review by the Director. Blank Not Permitted					
Notes: 1. Unless modified by Section 2 of this document, the land use definitions in Section 1.4 apply. 2. See individual Land Use Category Standards and Table 4 for the various types of SFD residential lots and minimum lot sizes allowed in each category. 3. Screening for Personal Recreational Vehicle Storage is required. 4. The maximum percentage allowed is defined to be the floor area of all non-residential uses divided by the gross area of the parcels (applicable only to HDR districts)					

B. Non-Residential Parcels

Table 8: Non-Residential Building and Lot Standards

Land Use Category		Minimum Building Setbacks	Minimum Parking Setback	Minimum Distance Building to Private Drive / Parking	Maximum Building Height	Minimum Building Separation	Maximum Floor : Area Ratio	Maximum Impervious Lot Coverage
Retail / Commercial	From College Dr. ROW	80'	75'	15'	50'	30'	0.30	75%
	From Collector St. ROW	25'	25'					
	From Parcel Boundary Line	25'	25'					
	From Internal Property Line	0'	0'					
Village Center	From College Dr. ROW	100'	75'	10'	40'	20'	0.40	75%
	From Collector St. ROW	25'	15'					
	From Internal Property Line	0'	0'					
Hospitality / Event Center	From College Dr. ROW	75'	50'	15'	60'	20'	0.50	90%
	From High Plains Rd. ROW	35'	25'					
	From Collector St. ROW	35'	25'					
	From Internal Property Line	0'	0'					
Medical Office	From Perimeter Arterial St. ROW	75'	50'	10'	35'	30'	0.25	80%
	From Collector St. ROW	25'	20'					
	From Parcel Boundary Line	25'	15'					
	From Internal Property Line	0'	0'					
Golf Course Clubhouse	From High Plains Rd. ROW	100'	100'	10'	50'	20'	0.40	75%
	From Collector St. ROW	100'	100'					
	From Parcel Boundary Line	0'	0'					
	From Internal Property Line	0'	0'					
Office / Retail	From Avenue 'C' ROW	100'	100'	15'	40'	20'	0.50	90%
	From Collector St. ROW	25'	20'					
	From Local St. ROW	25'	10'					
	From Parcel Boundary	50'	30'					
	From Internal Property Line	0'	0'					
School	From High Plains Rd. ROW	30'	35'	10'	35'	30'	0.25	40%
	From Collector St. ROW	25'	30'					
	From Local St. ROW	15'	20'					
	From Parcel Boundary	30'	20'					
	From Internal Property Line	0'	0'					
Park & Open Space Tracts	From College Dr. ROW	100'	75'	10'	Park: 50' OS: 35'	20'	Park: 0.40 OS: 0.10	Park: 25% OS: 15%
	From Avenue 'C' ROW	75'	50'					
	From High Plains Rd. ROW	75'	50'					
	From Local St. ROW	50'	50'					
	From Parcel Boundary Line	50'	30'					
	From Collector St. ROW	25'	20'					
	From Internal Property Line	0'	0'					
Ongoing Ranching Operations in the PUD shall be set back at least 200' from platted residential lots and at least 100' from non-residential buildings.								

1. Retail / Commercial

- Intent: The intent of Retail / Commercial parcels in Sweetgrass is to promote the development of retail and commercial stores, such as grocery stores and/or supermarkets, as well as big box retail development, to serve the greater southeastern Cheyenne area. Lodging is encouraged adjacent to College Drive because of proximity to the LCCC. Architectural design is intended to be prominent, particularly as seen from College Drive.
- Permitted Uses: Per Table 9.
- Building and Lot Standards: Per Table 8.

- d. **Architectural Design:** The Building Design standards in UDC Section 6.8.4 and 6.8.5 (Large Scale Commercial Design Standards) shall apply.
 - e. **Landscape Design:**
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.B.2.f of this PUD.
 - ii. For the purposes of landscape point calculations to determine minimum landscape material required, the impervious area shall be considered to be 80%.
 - iii. Landscape design of regional detention ponds shall be treated as a Naturalized Landscape per Section 3.B.2.e of this PUD.
 - iv. The western 30' of Parcel A and the southern 30' of Parcels A and B shall be landscaped as a Naturalized Landscape per Section 3.B.2.e of this PUD, subject to the standards described for a Level 2 Buffer in UDC Table 6-11. The intent of this buffer is to reduce the visual impact of the allowed uses on adjacent residential parcels, public parks and open space tracts.
- 2. Village Center**
- a. **Intent:** The Village Center intended to be the heart of the community, adjacent to the main entrance from South College Drive and directly across from a main entrance to the Laramie County Community College (LCCC). The Village Center is intended to provide a broad range of retail stores, service uses (e.g., post office annex, dry cleaner, barber, and similar), as well as business and professional offices, to Sweetgrass residents, students, and employees. Lodging is encouraged adjacent to College Drive because of proximity to the LCCC. The site design of the buildings and parking shall have a village character and be pedestrian-oriented. Outdoor seating will be an integral part of restaurants, coffee-shops, etc. A large central open space will be a major focal point for surrounding buildings and a community gathering space for outdoor activities. Such activities may include summer concerts and fairs, farmers' markets, ice-skating, and similar. Government uses, such as a fire station, police substation, etc., are encouraged, particularly between Murray Road and the central open space.
 - b. **Permitted Uses:** Per Table 9.
 - c. **Building and Lot Standards:** Per Table 8.
 - d. **Architectural Design**
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
 - e. **Landscape Design:**
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.B.2.f of this PUD.
 - ii. For the purposes of UDC landscape point calculations to determine minimum landscape material required, the impervious area shall be considered to be 60%.
 - iii. Landscape design of regional detention ponds shall be treated as a Naturalized Landscape per Section 3.B.2.e of this PUD.
- 3. Hospitality and Event Center**
- a. **Intent:** The intent of the Hospitality & Event Center district is to provide indoor and outdoor entertainment venues to local residents, college students, and visitors, as well as hotel and convention facilities conveniently located adjacent to the Laramie County Community College. In addition, upscale restaurants, specialty retail, and signature office space will be provided. The intersection of College Drive and High Plains Road will be the primary entrance to Sweetgrass; as such, large-scale monuments and prominent landscape design are planned for the southwest and southeast corners of the intersection.
 - b. **Permitted Uses:** Per Table 9.

- c. Building and Lot Standards: Per Table 8.
 - d. Architectural Design: The Building Design standards in UDC Section 6.8.4 and 6.8.5 (Large Scale Commercial Design Standards) shall apply.
 - e. Landscape Design:
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.B.2.f of this PUD.
 - ii. For the purposes of landscape point calculations to determine minimum landscape material required, the impervious area shall be considered to be 80%.
4. Medical Office Campus
- a. Intent: The intent of the Medical Office Campus use on Parcel F is to allow for the development of a medical office campus in an easily accessible location convenient to the Laramie County Community College, with the potential for other related uses.
 - b. Permitted Uses: Per Table 9.
 - c. Building and Lot Standards: Per Table 8.
 - d. Architectural Design:
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
 - e. Landscape Design:
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.B.2.f of this PUD.
 - ii. Landscape design of naturalized landscapes and/or areas in close proximity to the golf course shall be treated as a Naturalized Landscape per Section 3.B.2.e of this PUD.
5. Golf Course Clubhouse
- a. Intent: The intent of the Golf Course Clubhouse District is to allow the development of an upscale resort and convention center focused on the golf course, tennis facilities, swimming pool, stables, and/or equestrian facilities. Guest facilities may be stand-alone suites or attached villas, within a traditional hotel, or a combination thereof. The tennis club and/or equestrian arena may include stadium seating. Portions of the site may host outside events, such as weddings, parties, and other gatherings. Clubhouses will include food and beverage service, as well as locker rooms, swimming pool(s), golf cart storage and maintenance, and other uses commonly found in such. A portion of the Parcel may be developed as High Density Residential, depending upon market conditions.
 - b. Permitted Uses: Per Table 9.
 - c. Building and Lot Standards: Per Table 8. Note that the setbacks in the HDR district will apply for any residential development proposed in Parcel J.
 - d. Architectural Design:
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
 - e. Landscape Design:
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.B.2.f of this PUD.
 - ii. Landscape design of naturalized landscapes and/or areas in close proximity to the golf course shall be treated as a Naturalized Landscape per Section 3.B.2.e of this PUD.
 - iii. Adjacent non-compatible uses shall be separated at minimum by either: a Level 2 landscape buffer as described within UDC Table 6-11; or, by dedicated public right of way; or, by a private street corridor at least 50' in width.

6. Office / Research Campus

- a. Intent: The Office / Research Campus land use parcels are located along the western property boundary adjacent to the future extension of South Avenue C and in close proximity to State Highway 85 (South Greely Highway). This land use category is intended to provide a broad range of employment opportunities and business uses ranging from corporate campus, multi-tenant office buildings, research and development consistent with light industrial land uses, a potential extension of a college or university, as well as retail uses to support the above.
- b. Permitted Uses: Per Table 9.
- c. Building and Lot Standards: Per Table 8.
- d. Architectural Design:
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
- e. Landscape Design
 - i. Landscape design adjacent to buildings and parking lots shall be treated as an Irrigated Landscape per Section 3.8.2.f of this PUD.
 - ii. The eastern 30' of Parcels CC and DD shall be landscaped as a Naturalized Landscape per Section 3.8.2.e of this PUD, subject to the standards described for a Level 2 Buffer in UDC Table 6-11. The intent of this buffer is to reduce the visual impact of the allowed uses on adjacent residential parcels and open space tracts.

C. Park, School, and Open Space Tracts

1. Community Park

- a. Intent: The Community Park is to be dedicated to the City of Cheyenne and developed as a community park with athletic fields and associated amenities (e.g., picnic pavilions, restrooms, playgrounds, parking areas, etc.) serving s Cheyenne, along with stormwater detention facilities and regional trails to serve the Sweetgrass PUD connecting to Laramie County Community College. A detailed program and design for the Community Park will be determined separately by the City.
- b. Permitted Uses: Per Table 9.
- c. Alternative Uses: In the event that Tract 1 or portion(s) thereof are not accepted by the City of Cheyenne for the purposes of a Community Park, the list of permitted uses in the portion(s) not acquired may expand to include those allowed in the MDR – Medium Density Residential District as described within Table 9.
- d. Building and Lot Standards: Per Table 8 and the following:
 - i. Athletic fields, stands, and other gathering areas shall be located a minimum of 100' from any platted residential lot.
 - ii. Parking lots and drives shall be located a minimum of 50' from any platted residential lot.
- e. Landscape Design: Naturalized landscaped within the Community Park shall be consistent with the PUD naturalized areas.

2. Schools

- a. Intent: The intent of the district is to provide centrally located parcels to be acquired by the Laramie County School District and/or private school operators for the purpose of constructing elementary schools and a combined middle school / high school.
- b. Permitted Uses: Per Table 9.
- c. Alternative Uses: In the event that lands set aside for schools in the PUD are not acquired by a public school district or private educational provider within fifteen years of the adoption of this PUD, the list of Permitted Uses in this District will expand to include also those allowed in the MDR

district described within Table 9. The maximum number of units allowed in Sweetgrass will remain unchanged.

- d. Building and Lot Standards: Per Table 8.
- e. Fences: Alternative fence designs, including chain link fences, are allowed. Chain link fences may not be within 5' of the public right of way.
- f. Architectural Design
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 shall apply to private schools.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
 - iii. Buildings not meeting the above standards shall be screened from public right of way and adjacent residential properties with a an additional 10' width landscape buffer and landscape as described in UDC Table 6-11 (Level 1 buffer).
- g. Landscape Design:
 - i. Landscape design shall meet the standards described within Section 3.B.2.f (Irrigated Landscapes) of this PUD.
 - ii. For the purposes of landscape point calculations to determine minimum landscape material required, the impervious area shall be considered to be 90%.

3. Open Space

- a. Intent: The intent of Open Space tracts are to provide expanses of native prairie grasses, public trails, the continuation of existing ranching operations, stormwater conveyance and detention facilities, an eighteen hole golf course and practice facilities for public and/or private use, and golf maintenance facilities.
- b. Permitted Uses: Per Table 9.
- c. Building and Lot Standards: Per Table 8.
- d. Architectural Design:
 - i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 shall apply to private schools.
 - ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.
 - iii. Buildings not meeting the above standards shall be screened from public right of way and adjacent residential properties with a an additional 10' width landscape buffer and landscape as described in UDC Table 6-11 (Level 1 buffer).
- e. Landscape Design: Per Section 3.B.2.d (Native Landscapes) and Section 3.B.2.e (Naturalized Landscapes) of this PUD, as applicable. Irrigation and landscape design of the golf course are not subject to the standards within this PUD.

Table 9: Allowed Non-Residential Uses by Category

Proposed Land Uses		Retail / Commercial District	Village Center	Hospitality / Event Center	Medical Office	Golf Course Clubhouse	Office & Research Campus	Community Park	Elementary & Middle School	Open Space
Civic Uses	Neighborhood Assembly (< 350 person capacity)		P	P				P	P	
	Community Assembly (350-1000 person capacity)		P	P				P	P	
	Primary & Secondary Schools		A						P	
	Educational Facilities		P				P		A	
	Community Athletic Field							P	P	P
	Park Maintenance Facilities & Associated Offices							P		
	Developed Athletic Field / Stadium					P		P	P	
Service Uses	Service Businesses – Limited and General	P	P	P		A				
	Adult Care, Assisted Living and/or Nursing Home				P					
	Animal Care, Kennel				A					
	Animal Care, Hospital/Clinic	P	P		P			P		
	Child Care Center – Minor		P		P	P	P	P		
	Child Care Center – Major		P		P	P	P	P		
	Entertainment, Indoor Recreation Facility		A	P	P			P		
	Entertainment, Outdoor Recreation Facility (Golf)					P				P
	Entertainment, Outdoor Recreation Facility (non-Golf)			P				P		
	Entertainment Venue			P		P		P		
	Lodging, Hotel or Motel	P	P	P		P				
	Medical Care, Clinic				P					
Employment	Medical Care, Office		P		P					
	Office – Limited (<3,500 SF)	P	P				P			
	Office – General (3,500 – 20,000 SF)	P	P				P			
	Office – Major Complex (>20,000 SF)	P					P			
Industrial	Limited Industrial						P			A
	Moderate Industrial						A			
	Limited Outdoor Storage						A	P		A
Notes		1. Unless modified by Section 2 of this PUD, the land use definitions in UDC Section 1.4 apply. 2. Nothing in this PUD shall prohibit alcohol sales as a part of the golf course liquor license (i.e., beverage cart sales, etc.), subject to additional conditions outside of the scope of this PUD. 3. Limited industrial and outdoor storage uses in the OS District land use category are allowed only as part of the golf course maintenance operations.								
		Legend P Use Permitted by Right A Use Permitted by Administrative Review Blank Not Permitted								

(End of Section)

Appendix A: Sweetgrass PUD Street Sections

Table 10: Sweetgrass PUD Roadway Design Information

Street Section Reference	Perimeter Arterial	Urban Arterial	Rural Arterial	Urban Collector	Transitional Collector	Rural Collector
Description	4 – 6 lane regional arterial connecting US Hwy 85 to High Plains Rd. and SE Cheyenne ⁽²⁾	4 – lane arterial road transitioning between rural road section south of Murray Rd. to NB College Dr.	2 – lane arterial road connecting from Murray Road, south through low-density portions of Sweetgrass to Avenue. C.	2 – lane collector street with median, connecting College Dr. to Murray Rd. and most intensive land uses.	2 – lane collector street with median, separating "urban" portion of Sweetgrass from "rural" areas.	2 – lane collector street without median, providing circulation through "rural" areas.
Context	College Drive, at full buildout ⁽³⁾	High Plains Road (north of Murray Rd.)	High Plains Road (south of Murray Rd.)	Collector Streets north of Murray Rd. and south of College Dr.	Murray Rd, from Ave C to High Plains Rd and Future College Dr. extension.	Collector Streets, primarily south of Murray Road and "rural" areas.
Notes	(1) Local streets: The City's standard Residential (Type A) street section (UDC Figure 4-8) is proposed for public streets in residential parcels. Alternative street sections with a narrower width or other changes may be approved on a case-by-case basis in low-traffic volume situations. (2) Avenue C is proposed to be improved as a Minor Arterial, per UDC Table 4-5. (3) WYDOT will be responsible for the ultimate design and construction of College Drive. These improvements are anticipated following the Third Filing. Acceleration or deceleration lanes required to implement the first three filings will be coordinated by the Committee.					

Table 11: Roadway Technical Criteria

Street Section Reference	Perimeter Arterial	Urban Arterial	Rural Arterial	Urban Collector	Transitional Collector	Rural Collector
Design Speed	50 mph	45 mph	40 mph	35 mph	35 mph	35 mph
Posted Speed Limit	45 – 50 mph	35 mph	30 mph	30 mph	30 mph	30 mph
Design Vehicle	WB – 67	WB – 67	WB – 50	SU – 30	SU – 30	SU – 30
Min. Sight Distance	1,030'	830'	660'	660'	660'	660'
Stopping Sight Distance	400'	325'	200'	200'	200'	200'
Min. Intersection Spacing	1,320'	330'	330'	330'	330'	330'
Distance Between Signals	2,640'	N/A	N/A	N/A	N/A	N/A
Driveway Approach & Street Config.	Radial curb return (no direct driveway access)	Radial curb return or roundabout	Radial curb return	Radial curb return	Radial curb return	Radial curb return
Curb & Gutter Type	6" vertical	6" vertical	None	6" vertical	None	None
Grade (max. / min)	6% / 0.50%	6% / 0.50%	8% / 0.5%	8% / 0.5%	8% / 0.5%	8% / 0.5%

Table 12: Geometric & Urban Design Standards

Street Section Reference	Perimeter Arterial	Urban Arterial	Rural Arterial	Urban Collector	Transitional Collector	Rural Collector
A Right of Way Width	140' Typ. (varies)	120' ⁽²⁾	100'	100' ⁽²⁾	100'	100'
B Roadway Width	Varies	78' (BOC – BOC)	50' (EOA – EOA)	(61' BOC – BOC)	52' (EOA – EOA)	36' (EOA – EOA); 46' (EOA – EOA) with parking on one side
C Lane Width (# lanes)	12' (4 – 6 lanes)	12' (4 lanes)	12' (2 lanes)	12' (2 lanes)	12' (2 lanes)	12' (2 lanes)
D Bike Lane & Shoulder Width ⁽¹⁾	7' Bike Lane / Shoulder	6' Bike Lane / Shoulder	8' Bike Lane / Shoulder	8' Bike Lane / Shoulder	6' Bike Lane / Shoulder	6' Bike Lane (10' optional parking lane outside of the bike lane)
E Median	Landscaped raised, 20' width (8' min. width w/ turn lanes)	Landscaped, raised. 17' width BOC – BOC standard; 7' width BOC – BOC w/ left turn.	Optional (may be raised with curb & gutter or depressed for drainage, or no median)	Landscaped, raised. 19' width BOC – BOC standard; 7' width BOC – BOC w/ left turn.	Landscaped, raised. 11' width BOC – BOC; 1' width BOC – BOC (concrete) w/ left turn.	None.
F Concrete Sidewalk	South side: None ⁽²⁾	6' width (one side)	6' width (one side)	6' width (one side)	6' width (one side)	None.
G Tree Lawn	South side: Varies ⁽²⁾	12' width (one side)	12' width (one side)	12' width (one side)	12' width (one side)	None.
H Regional Trail	10' width, one side (meandering in easement and ROW; detached from street; returns to curb at intersections to allow safe pedestrian crossings)					
I Trail / Utility Easement	75' min. South side	50' (one side)	50' (one side)	50' (one side)	50' (one side)	50' (one side)
Notes	(1) Parking will not be permitted along arterials and collectors. (2) Adjacent property owners will be responsible for design and construction of sidewalk and landscape improvements north of College Drive and west of Avenue C. (3) Trail alignments may vary slightly from those illustrated in street sections because of grading, utilities, and other constraints.					

Street Sections Proposed

Perimeter Arterial Street Section	Page A-3
Urban Arterial Street Section	Page A-3
Rural Arterial Street Section	Page A-4
Urban Collector Street Section	Page A-4
Transitional Collector Street Section	Page A-5
Rural Collector Street Section	Page A-5
Rural Collector with Parking Lane	Page A-6

Please refer to the Sweetgrass Final Planned Unit Development (sheet 3 of 6) for applications of the above street sections.




Figure 2: Perimeter Arterial Street Section




Figure 3: Urban Arterial Street Section




Figure 4: Rural Arterial Street Section




Figure 5: Urban Collector Street Section




Figure 6: Transitional Collector Street Section




Figure 7: Rural Collector Street Section




Figure 8: Rural Collector with Parking Lane

(End of Appendix)

Appendix B: Sweetgrass Final PUD Drawings

(Reserved for six PUD drawings, as recorded)

(End of Appendix)

**This page intentionally left blank
for two-sided printing.**

**Sections 15, 16, and 21, plus Portions of Sections 10, 11, and 14,
Township 13, Range 56 West, of the Sixth Principal Meridian,
to the City of Cheyenne, Wyoming**

Approved by the City of Chicago Planning Commission on _____ day of _____ 20____

City Council Approval

Approved by the Council of the City of Cheyenne Wyoming on _____ day of _____ 20____

Age of

Overnight Shipping

_____ **DATE** _____

Acknowledgement

CONTRACTS OF SALE

The foregoing instrument may be impounded before the date of _____ 20____

By David E. Lathrop, Managing Member of the Strategists Land Co., LLC, and President of Aep & Homestead Hardware Co., a Wyoming Corporation

[illegible]

My Commission Expires

The following parcels of land situated in Township 13 North, Range 66 West of the 6th P. M., Cherokee, Jackson County, Wyoming, described as follows:

163 The Southeast Division of the Environmental Protection Agency (USEPA/SEDO) at 2-2000.

The growth level of the growth level of the - observations minus observations - 0.5 = . . .

1. **Identify the author's main purpose in writing this passage.**

The West Hill (WH) of Sordani 12.

Adj of Section 15.

All of Section 18 being under of College One right-of-way and EXCEPT that

Laramie County Wyoming records described as follows: Beginning at a point on

On 14th June of 1961 Section 18 began where the North-west corner turned (near NO. 111111) a distance of 11114 ft. Section 18 00-43.47 ft. distance to

160 00 Ave. George & C^o 5727 W., a balance of 100.00. Balance N 09° 47' 57" W., a

It would not be long (2016), for example, if they were to have 3,150,000

There is always something different about the people who work for us.

A4 of Section 21.

Why is there such a big difference between the two?

100

Sheet Index

Sheet 1 Cover Sheet

Sheet 2
Sheet 3

Sheet 4
Monument & Fence Plan & Details

Sheet 5
Planning Diagram Exhibit

Sheet 6
Supergrass Master Greenway & Trails Exhibit


100


Prepared for:

[illegible]

**Southwest
Planned Unit Development**

1 OF 6





Project No.
Map Scale
Map Date


Sweetgrass
Planned Unit Development
- DRAFT -
Final PUD Map Exhibits
City of Cheyenne, Wyoming

Sweetgrass
Planned Unit Development
- DRAFT -
Final PUD Map Exhibits
City of Cheyenne, Wyoming


Sweetgrass
Planned Unit Development
- DRAFT -
Final PUD Map Exhibits
City of Cheyenne, Wyoming

Sheet No.	1 of 6
Map Scale	1" = 100'
Map Date	10/1/00
Map Title	Site Analysis Map

2 of 6



Site Analysis Map



Project No. 10000
 State of Wyoming
 Professional Engineer
 License No. 10000
 Date 10/1/2010



Sweetgrass
 Final P.U.D. Map Exhibit
 Planned Unit Development
 City of Cheyenne, Wyoming



Area	Acres
Zone 1	1.2
Zone 2	1.5
Zone 3	1.8
Zone 4	2.1
Zone 5	2.4
Zone 6	2.7
Zone 7	3.0
Zone 8	3.3
Zone 9	3.6
Zone 10	3.9
Zone 11	4.2
Zone 12	4.5
Zone 13	4.8
Zone 14	5.1
Zone 15	5.4
Zone 16	5.7
Zone 17	6.0
Zone 18	6.3
Zone 19	6.6
Zone 20	6.9
Zone 21	7.2
Zone 22	7.5
Zone 23	7.8
Zone 24	8.1
Zone 25	8.4
Zone 26	8.7
Zone 27	9.0
Zone 28	9.3
Zone 29	9.6
Zone 30	9.9
Zone 31	10.2
Zone 32	10.5
Zone 33	10.8
Zone 34	11.1
Zone 35	11.4
Zone 36	11.7
Zone 37	12.0
Zone 38	12.3
Zone 39	12.6
Zone 40	12.9
Zone 41	13.2
Zone 42	13.5
Zone 43	13.8
Zone 44	14.1
Zone 45	14.4
Zone 46	14.7
Zone 47	15.0
Zone 48	15.3
Zone 49	15.6
Zone 50	15.9
Zone 51	16.2
Zone 52	16.5
Zone 53	16.8
Zone 54	17.1
Zone 55	17.4
Zone 56	17.7
Zone 57	18.0
Zone 58	18.3
Zone 59	18.6
Zone 60	18.9
Zone 61	19.2
Zone 62	19.5
Zone 63	19.8
Zone 64	20.1
Zone 65	20.4
Zone 66	20.7
Zone 67	21.0
Zone 68	21.3
Zone 69	21.6
Zone 70	21.9
Zone 71	22.2
Zone 72	22.5
Zone 73	22.8
Zone 74	23.1
Zone 75	23.4
Zone 76	23.7
Zone 77	24.0
Zone 78	24.3
Zone 79	24.6
Zone 80	24.9
Zone 81	25.2
Zone 82	25.5
Zone 83	25.8
Zone 84	26.1
Zone 85	26.4
Zone 86	26.7
Zone 87	27.0
Zone 88	27.3
Zone 89	27.6
Zone 90	27.9
Zone 91	28.2
Zone 92	28.5
Zone 93	28.8
Zone 94	29.1
Zone 95	29.4
Zone 96	29.7
Zone 97	30.0
Zone 98	30.3
Zone 99	30.6
Zone 100	30.9



0 500 1,000
 Feet
 0 500 1,000
 Meters

Planned Unit Development Land Use Map

City of Cheyenne, Wyoming
 Planning Department
 1000 Main Street, Suite 100
 Cheyenne, WY 82001
 (307) 733-1234



David A. Lee
Professional Engineer
State of Wyoming
License No. 10000
Mechanical Engineering
12/15/2018




Prepared By
Sweetgrass Engineering

Sweetgrass
Planned Unit Development
Final P.U.D. Map Exhibits
City of Cheyenne, Wyoming




NO.	DATE	DESCRIPTION
1	12/15/2018	Final P.U.D. Map Exhibits
2	12/15/2018	Final P.U.D. Map Exhibits
3	12/15/2018	Final P.U.D. Map Exhibits
4	12/15/2018	Final P.U.D. Map Exhibits
5	12/15/2018	Final P.U.D. Map Exhibits
6	12/15/2018	Final P.U.D. Map Exhibits
7	12/15/2018	Final P.U.D. Map Exhibits
8	12/15/2018	Final P.U.D. Map Exhibits
9	12/15/2018	Final P.U.D. Map Exhibits
10	12/15/2018	Final P.U.D. Map Exhibits


Sheet No. 4 of 6
4 of 6



Fence & Monument Plan




Major Entry Monument Detail
Scale: 1/8" = 1'-0"



Double-Sided Privacy Fence Detail
Scale: 1/8" = 1'-0"




Open Rail Fence Detail
Scale: 1/8" = 1'-0"




Metal Picket Fence Detail
Scale: 1/8" = 1'-0"

Residential Neighborhood Identifier
Scale: 1/8" = 1'-0"



Non-Residential Neighborhood Identifier
Scale: 1/8" = 1'-0"






Phasing Diagram Exhibit

Proposed Boundary		Acres		Total Acres		Total Acres	
Phase	Area	Phase	Area	Phase	Area	Phase	Area
1	1.00	2	1.00	3	1.00	4	1.00
5	1.00	6	1.00	7	1.00	8	1.00
9	1.00	10	1.00				

1. The Phasing Plan is intended to be a general guide to the development of the project and is not intended to be a final plan of record.

2. The Phasing Plan is intended to be a general guide to the development of the project and is not intended to be a final plan of record.

3. The Phasing Plan is intended to be a general guide to the development of the project and is not intended to be a final plan of record.



Trails Legend

Trail Type	Width	Length	City	Map Scale
Cherry Creek Greenway Trail	12' width / 10' concrete	0.13 miles LP	N/A	1 inch = 400 feet
Regional Trail	12' width / 10' concrete	0.13 miles LP	N/A	1 inch = 400 feet
Low Impact Trail	8' width / 10' concrete	0.13 miles LP	N/A	1 inch = 400 feet



Master Trails Exhibit

Appendix C: Cheyenne UDC Sections Incorporated by Reference

Subject	Sweetgrass Final PUD Standards & Guidelines Text	UDC Section
Section 1: General Provisions		
B: Application (p. 1)	2. This PUD both references and diverges from the regulations contained in the Cheyenne Unified Development Code (UDC). 3. When the UDC is referenced herein, those sections of the UDC are shown in Exhibit B to this PUD document. 4. Portions of the PUD are more stringent than the UDC; others are less stringent and/or provide a different approach. If the PUD does not address a specific item, the most current edition of the Cheyenne UDC shall govern; otherwise, this PUD shall govern.	General
D. Density Variations and Transfers (p. 2)	5. An increase of dwelling units within a receiving parcel by more than 10% beyond the maximum described in the PUD may be accomplished through an Administrative Adjustment, as described in UDC Section 2.3.4, so long as the increase does not adversely affect the delivery of public services or substantially change the character of the PUD.	UDC §2.3.4
H. PUD Amendments (p. 3)	1. From time to time, this PUD may require an amendment as conditions in the area evolve or other changes occur. The Committee is authorized to act on behalf of Sweetgrass owners and residents to petition the Director to make minor amendments to this PUD, subject to the procedures outlined in UDC Section 2.3.4 – Administrative Adjustment. Such amendments could include text amendments that do not affect materially the nature of the PUD, adjustments to parcel boundaries, changes to trail alignments, and/or other, similar items.	UDC §2.3.4
	2. In the event that the Director finds that a proposed amendment is outside of the minor adjustments described within UDC Section 2.3.4.b.2, the Committee is authorized to act on behalf of Sweetgrass owners and residents to petition the Planning Commission for an amendment to this PUD pursuant to UDC Sec. 5.6.2.h.	UDC §5.6.2
J. Temporary Uses (p. 3)	4. The temporary uses permitted by City of Cheyenne as allowed with a "Temporary Use Permit" issued by the City of Cheyenne, pursuant to UDC Section 2.2.6.	UDC §2.2.6
L. Applications, Phasing, and Process (p. 4)	1. Following PUD adoption, the owners of PUD parcel(s) may submit site plans and/or plats for approval by the City of Cheyenne, as applicable. Such applications shall include a letter of endorsement from the Committee to be considered by the City. To receive a letter of endorsement, the applicant shall demonstrate to the satisfaction of the Committee that the applicant's plans and building concepts coincide with the goals and standards described within this PUD and the UDC, as applicable.	General
M. Street Sections (p. 4)	1. Because of the size of Sweetgrass, its rural character, and the goal of reducing public infrastructure and associated maintenance costs, alternative public street sections to the City's standard for collector and arterial streets (UDC §4.3) within and adjacent to Sweetgrass are	UDC §4.3 &

Subject	Sweetgrass Final PUD Standards & Guidelines Text	UDC Section
	a part of this PUD. Street sections allowed in Sweetgrass are illustrated in Appendix A of these Standards & Guidelines.	
	2. The Sweetgrass Street Sections may be adjusted slightly as construction plans are developed for special circumstances, such as roundabouts, accel or decel lanes, turning lanes, and/or other conditions, without amending this PUD and/or necessitating a formal Waiver to Subdivision Standards.	UDC §2.3.1
Section 2: Definitions		
A. Purpose (p. 5)	2. Refer to the current Cheyenne Unified Development Code for other definitions not defined herein.	General
B. Word Usage (p. 5)	1. In the interpretation of this Planned Unit Development, the provisions and rules of this section shall be observed and applied, except when the context requires otherwise. For definitions not found below, refer to Section 1.4 of the Cheyenne Unified Development Code; otherwise, the accepted dictionary definition in normal context shall apply.	UDC §1.4
Section 3: Development Standards & Guidelines		
A. Residential Parcels (p. 8)	2. Street and Building Orientation around Neighborhood Parks and Schools	General
	3. Anti-Monotony Criteria	UDC §6.6.3.b.2
	4. Neighborhood Edges	General
	5. Exterior Materials	UDC §6.6.3.b.3
	6. Roof Design	General
	7. Front Porch Requirements	UDC §6.6.4.b.1
	8. Garages and Driveways	UDC §6.6.4.a.4 & Figure 6-7
	9. Residential Lighting	General
	10. Internal Parks and Open Space	UDC §4.411.
	11. Fences, Entry Monuments, and Retaining Walls	UDC §5.8.4
	12. Common Recreational Vehicle Storage and Screening	General
B. Non-Residential Parcels (p. 12)	2. Landscape Design	UDC §6.3
	g. Irrigated Landscapes	Table 6-8
	ii. Minimum Plant Materials Required	
	(a) Trees: Per UDC Section 6.3 Tree Points, Table 6-8	
	(b) Shrubs & Groundcovers: per UDC Section per UDC Section 6.3, Table 6-9, except that points shall be awarded for only shrubs, flowering perennials, and ornamental grasses.	Table 6-9
	3. Lighting	UDC §6.4
	4. Signs, Fences, and Entry Monuments	UDC §6.5
	5. Parking Requirements	UDC §6.2
Section 4: Land Use Regulations		
A. Residential Parcels (p. 19)	Tables 4 & 5	General
	3. Access to Residential Parcels: Because Sweetgrass is a series of neighborhoods designed within a planned collector street network	UDC §4.3.3.f.3(a)-(d)

Subject	Sweetgrass Final PUD Standards & Guidelines Text	UDC Section
	around a significant open space system, the access guidelines contained within UDC §4.3.3.f.3(a) – (d) are not applicable. Residential development parcels shall provide access sufficient for emergency vehicles (per International Fire Code, as adopted by the City when the final plat for the residential parcel is submitted), with a minimum Level of Service of "C."	
	4. Streets within Residential Parcels a. SFD Residential Neighborhoods: Streets shall be dedicated public right of way per UDC "Standard Roadway: Residential."	UDC §4.3
B. Non-Residential Parcels (p. 25)	Table 8	General
	1. Retail / Commercial d. Architectural Design: The Building Design standards in UDC Section 6.8.4 and 6.8.5 (Large Scale Commercial Design Standards) shall apply.	UDC §6.8.4 & §6.8.5
	2. Village Center d. Architectural Design i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply. ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.	UDC §6.9.4 & §6.9.5
	3. Hospitality and Event Center d. Architectural Design: The Building Design standards in UDC Section 6.8.4 and 6.8.5 (Large Scale Commercial Design Standards) shall apply.	UDC §6.8.4 & §6.8.5
	4. Medical Office Campus d. Architectural Design: i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply. ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.	UDC §6.9.4 & §6.9.5
	5. Golf Course Clubhouse d. Architectural Design: i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply. ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.	UDC §6.9.4 & §6.9.5
	5. Office / Research Campus d. Architectural Design: i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 (General Commercial Design Standards) shall apply. ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.	UDC §6.9.4 & §6.9.5

Subject	Sweetgrass Final PUD Standards & Guidelines Text	UDC Section
	e. Landscape Design: ii. The eastern 30' of Parcels CC and DD shall be landscaped as a Naturalized Landscape per Section 3.B.2.e of this PUD, subject to the standards described for a Level 2 Buffer in UDC Table 6-11. The intent of this buffer is to reduce the visual impact of the allowed uses on adjacent residential parcels and open space tracts.	UDC Table 6-11
C. Park, School, and Open Space Tracts (p. 28)	2. Schools f. Architectural Design i. The Building Design standards in UDC Section 6.9.4 and 6.9.5 shall apply to private schools. ii. Building material calculations identified in UDC Section 6.9.4.e (Table 6-21) shall be calculated only for the first 12' above finished floor elevation.	UDC §6.9.4 & §6.9.5
	iii. Buildings not meeting the above standards shall be screened from public right of way and adjacent residential properties with a an additional 10' width landscape buffer and landscape as described in UDC Table 6-11 (Level 1 buffer).	UDC Table 6-11
Appendix A: Sweetgrass PUD Street Sections		
Table 10 (p. A-1)	(1) Local streets: The City's standard Residential (Type A) street section (UDC Figure 4-8) is proposed for public streets in residential parcels. Alternative street sections with a narrower width or other changes may be approved on a case-by-case basis in low-traffic volume situations. (2) Avenue C is proposed to be improved as a Minor Arterial, per UDC Table 4-5.	UDC Figure 4-8 and Table 4-5
Tables 11 & 12 (p. A-1)	Roadway Technical Criteria and Geometric & Urban Design Standards	UDC §4, General
Figures 2 – 8 (p. A-3)	Sweetgrass PUD Street Sections	UDC §4, General

(End of Appendix)



March 22, 2018

Sweetgrass P.U.D. Impact Assessment

Legal Description

The following parcels of land situated in Township 13 North, Range 66 West of the 6th P.M., Laramie County, Wyoming, described as follows:

The Southeast Quarter of the Southeast Quarter (SE $\frac{1}{4}$ SE $\frac{1}{4}$) of Section 10.

The South Half of the South Half of the West Half (S $\frac{1}{2}$ S $\frac{1}{2}$ W $\frac{1}{2}$) of Section 11.

The West Half (W $\frac{1}{2}$) of Section 14.

All of Section 15.

All of Section 16 lying south of College Drive right-of-way line and EXCEPT that parcel recorded June 26, 1991 by Warranty Deed filed in Book 1304 Page 1805, Laramie County, Wyoming records described as follows: Beginning at a point on the West line of said Section 16, from which the Northwest corner thereof bears N.0°50'32"E., a distance of 1320.58 feet; thence S.89°42'54"E., a distance of 160.00 feet; thence S.0°50'32"W., a distance of 160.00; thence N.89°42'54"W., a distance of 160.00 feet to a point on the West line of said Section 16; thence N.0°50'32"E., along said West line, a distance of 160.00 feet to the point of beginning. Exception containing 0.5877 acres more or less.

All of Section 21.

All of the above containing 2349.54 acres more or less.

Existing Conditions

The property is undeveloped pasture and open range, with a ridge running from the southwest to the northeast. The Lummis family has grazed cattle on the property for multiple generations. No hazardous materials, toxins, or underground storage tanks are known to be on the property.

Vegetation is native and introduced grasses and herbaceous plants suitable for grazing. A few woody plant species, both natives and exotics, can be found in sheltered draws. To the best of our knowledge, no significant historic or cultural sites are on the property. The site appears to include no significant habitat for threatened and endangered species, although a formal ecological characterization report has not been prepared.

Because the ridge is important visually to the community as a whole, development will be generally northwest of the ridge. The northeast portion of the property is subject to flooding, mainly from a large watershed south and west of the property flowing to the Allison Draw.

Existing zoning of Sweetgrass is PUD, in unincorporated Laramie County, as adopted in 2013. The City of Cheyenne's Comprehensive Plan reflects the form of the Sweetgrass PUD from that time as well.

The open lands south and east of Sweetgrass are A-2, Agricultural in unincorporated Laramie County. The properties west of Avenue C have multiple zoning designations, also in unincorporated Laramie County. These ranging from agricultural to various residential designations, and light industrial.

The property is currently accessed via E. College Drive and Avenue C. Both streets are to be extended, as called for in the City's Comprehensive Plan. Multiple arterial streets and collector streets are proposed to connect to the existing Cheyenne grid. Sweetgrass represents the southeastern edge of the area contemplated for development, and streets are not proposed to extend beyond Sweetgrass (with the exception of Avenue C and the extension of College Drive), the gridded street system is modified in Sweetgrass. Most planned existing east – west major streets, connect through Avenue C, and terminate at the proposed Sweetgrass Drive, about a quarter mile east of Avenue C.

The Laramie County Community College is north of College Drive from the property.

Proposed Development

The most intense development will be adjacent to College Drive and Avenue C, with lower intensities and densities proposed moving further south and east. Commercial, retail, hospitality, entertainment, and other uses are proposed along College. Student housing is proposed within walking distance of the LCCC, with varying densities elsewhere, up to lots greater than an acre each. As open space is a major component of Sweetgrass, some 886 acres – about 38% of the gross property area – will be parks and open lands, much of which will be undeveloped prairie uplands. This total excludes open lands within each development parcel. A golf course has been routed through the property, although at this time, the golf course is not planned to be constructed in an early phase.

A phasing plan has been prepared for Sweetgrass to allow development to occur gradually and in an organized manner across the property. Ten phases are proposed, at about five years per phase. Of course, this timing will be subject to market conditions. For example, it may be possible to construct the golf course and golf course clubhouse prior to the fifth phase, if the developer elected to construct temporary infrastructure required to do so. Assuming a start year of 2018, construction of the final phase will be completed in 2068, as shown in the Phasing Table below.

Assumed Start: 2018	Residential Parcels			Non-Residential Parcels		
	Parcel	± Area (Acres)	Min - Max Units	Parcel	± Area (Acres)	Maximum Floor Area (SF)
Phase 1	BB	37.0	370 – 888	East A	4.2	24,700
				B	15.6	280,000
				West C	3.1	13,500
Subtotal / Year 2023:		37.0	370 – 888		22.9	318,200
Phase 2	AA	22.5	90 – 225	West A	16.7	176,000
	CC	10.7	107 – 257			
Subtotal:		33.2	197 – 482		16.7	176,000
Completed by Year 2028:		70.2	567 – 1,370		90.0	494,200
Phase 3	Z	60.5	242 – 605	East C	12.9	40,500
				D	35.5	785,000
Subtotal:		60.5	242 – 605		48.4	825,500
Completed by Year 2033:		130.7	809 – 1,975		90.0	1,319,700
Phase 4	X	99.9	400 – 999			
	Y	43.1	431 – 1,034			
Subtotal:		143.0	831 – 2,033			
Completed by Year 2038:		273.7	1,640 – 4,008		90.0	1,319,700
Phase 5				J	39.1	680,000
Subtotal:					39.1	680,000
Completed by Year 2043:		273.7	1,640 – 4,008		127.0	1,999,700
Phase 6	L	15.7	157 – 377	E	12.2	270,000
	K	41.8	84 – 167	F	11.2	120,000
	M	36.0	144 – 360			
	N	31.8	127 – 318			
Subtotal:		125.3	512 – 1,222		23.6	390,000
Completed by Year 2048:		399.0	2,152 – 5,000*		113.6	2,389,700
Phase 7	O	38.5	77 – 154			
	P	45.8	92 – 183			
	Q	61.7	123 – 247			
Subtotal:		146.0	292 – 584			
Completed by Year 2053:		545.0	2,444 – 5,000*		113.6	2,389,700
Phase 8	R	145.5	15 – 291			
Subtotal:		145.5				
Completed by Year 2058:		690.5	2,459 – 5,000*		113.6	2,389,700
Phase 9	S	31.6	63 – 126	T	30.6	665,000
	W	47.7	95 – 191	U	20.4	445,000
				V	30.9	675,000
Subtotal:		79.3	158 – 317		81.9	1,785,000
Completed by Year 2063:		769.8	2,617 – 5,000*		195.5	4,415,000
Phase 10	G	69.6	7 – 139			
	H	28.4	3 – 57			
	I	63.5	6 – 127			
Subtotal:		161.5	16 – 323			
Completed by Year 2068:		931.3	2,633 – 5,000*		195.5	4,415,000
* Residential Units capped @ 5,000 DU.						

Public & Private Services

Stormwater Management: The Allison Draw, a tributary of Crow Creek, is north of the property. All of the areas within Sweetgrass proposed to be developed ultimately drain to the Allison Draw. Portions of Sweetgrass are within the 100-year floodplain, most notably near Avenue C, as well as near the future intersection of College Avenue and High Plains Road. Floodplains in these areas will be affected as development progresses.

The southeast corner of Avenue C and College Drive will be a regional pond to serve areas generally west of Cattle Drive; other parts of the property will drain (for the most part) through the golf course. While golf design has not progressed beyond preliminary routing plans, it is assumed that areas north of Murray and east of Cattle Drive will drain to stormwater detention and retention facilities designed in conjunction with the golf course. Developed areas south of Murray Road and north of College will, in all likelihood, have separate drainage infrastructure.

It should be noted that the undeveloped lands south of the ridgeline along the southern boundary of Sweetgrass drain generally south and east to an unnamed tributary of Porter Draw.

Sanitary Sewer: The Board of Public Utilities recently completed a 30" sanitary sewer line along Avenue C, and north to the Allison Draw below College Avenue (east of the LCCC). This line will serve the first phase of Sweetgrass, and areas generally west of Sweetgrass Drive. North of the Sweetgrass PUD, the line will turn east, flow north of Laramie County Community College, and return to the north at College Avenue. A 24" stub is to be constructed along the new north-south College alignment, to the intersection of College Avenue and High Plains Road. This 24" stub will serve the remainder of the Sweetgrass PUD. While final utility plans will be prepared as the Sweetgrass PUD develops, no capacity issues are anticipated.

Water: The Board of Public Utilities recently constructed a water line, varying in diameter from 30" to 36", paralleling Avenue C and College Avenue. The water systems within Sweetgrass have not been designed; however, no capacity issues are anticipated.

Traffic: A separate traffic study has been prepared. As discussed previously, College Drive is an arterial to be widened to six lanes. Three signals are proposed on College Drive: at Avenue C, at Cattle Drive, and at High Plains Road. We anticipate that the College / Avenue C signal will be constructed following the first phase, or late in the first phase, when warranted. Other than the intersection with College Drive, no signals are contemplated on High Plains Road. Please note that Item 14 of the Sweetgrass PUD Master Annexation Agreement includes identifies Transportation Impact Fees specific to the Sweetgrass PUD that will be used to mitigate transportation impacts generated by the development of Sweetgrass.

Dry Utilities: Black Hills Energy serves the area. No capacity issues are anticipated.

Fire: The nearest Cheyenne Fire Department station is at W. 19th Street and Snyder Avenue, about 3.7 miles from Sweetgrass. Drive time to the nearest corner of Sweetgrass is approximately 9 minutes (in normal traffic conditions, per Google Maps). A typical coverage radius for a single fire station in Cheyenne is approximately 1.5 miles. Therefore, a fire station has been proposed in Parcel B (Village Center) to improve response times for the initial phases of Sweetgrass. Current CFD policy is for each station to employ 12 full-time equivalent positions, plus equipment.

Until the station described above is acquired and constructed, poor fire response times will need to be mitigated. As the Laramie County Fire District 1 station is at Allison Road and I-25 (about a mile

north of Sweetgrass), it is recommended that the CFD and LCFD agree to have the LCFD Station #1 serve the Sweetgrass PUD.

Because of the size of Sweetgrass, additional fire station locations will be identified for acquisition in future phases, presumably in or near Parcels U, V, or T (near the southwestern corner of the Sweetgrass PUD). Other fire station locations may be considered on a case-by-case basis.

Police: The nearest Cheyenne Police Department station is at Pioneer Ave and W 18th St., approximately 3.3 miles from Sweetgrass. Drive time is approximately 8 minutes (per Google Maps). Land has been allocated for a police substation in Parcel B (Village Center) to improve response times. Because police substations tend to be small, the facility may be incorporated within another building, such as the fire station or library. Until this facility is constructed, at least some security in Sweetgrass may be provided privately, through a separate agreement with Laramie County, or a combination of these and potentially other approaches.

Library: The Cheyenne Public Library is located at Pioneer Ave. and W. 22nd St., about 3.7 miles from Sweetgrass. The Laramie County Public Library System, which also has branches in Burns and Pine Bluffs, intends to construct an additional branch in South Cheyenne. This branch which would serve Sweetgrass, as well as areas in and near Cheyenne south of I-80. Therefore, land has been identified for a branch library near the northwest corner of Sweetgrass Drive and Murray Road, pending funding for land acquisition and construction. Depending on market conditions and other factors, it may be possible for the building to be shared among multiple users, such as a police substation or retail and office uses.

Public Schools: Sweetgrass is in the Laramie County School District #1 South Triad. Schools serving the property today – before schools are constructed within Sweetgrass – would be Arp Elementary School, Johnson Junior High School, and South High School.

Arp Elementary School is at Reiner Court and Avenue C, about 0.7 miles north of the property. Arp Elementary School is currently at its capacity. Other elementary schools in the South Triad may have additional capacity in the short term. Because of the distance and number of students, two elementary schools are proposed in Sweetgrass. One could be constructed as early as the second phase of construction (within 5 – 10 years), while the second could be constructed following the fifth phase of construction (about 25 years).

Middle School / High School: Johnson Junior High School is at West Allison Road and South Cribbon Avenue, about 2.1 miles from Sweetgrass. Triumph High School, at College Drive and Park Avenue, is about 1.4 miles from Sweetgrass. The number of students generated from Sweetgrass alone would not warrant the construction of a new combined high school / middle school; however, we understand that these schools are currently at or near capacity. Therefore, a combined high school / middle school site is proposed near the intersection of Wallick Road and Avenue C, in Sweetgrass. Please note that this school is co-located with a community park to allow for potential of sharing athletic field use and leveraging funding.

The elementary school proposed at the southeast corner of Sirocco and Sweetgrass Drives could be constructed as early as the second phase (with the Sirocco Drive connecting Murray Road to Sweetgrass Drive). Current policy is to allocate funds for land acquisition and school construction only after a demand for students exists. Therefore, in the short term, the above schools would see increased student population as a result of Sweetgrass. Increases in student population would be

mitigated by bussing students to other schools below capacity in the South Triad. Once schools are constructed in Sweetgrass, the impacts to schools outside of Sweetgrass would presumably subside.

In the event that the District elects not to acquire Sweetgrass land set aside for schools, the owner will retain the right to develop the school parcels as HDR – High Density Residential, as described in the PUD Standards and Guidelines.


Emergency Medical Care: The nearest emergency room to Sweetgrass is the Cheyenne Regional Medical Center, at Warren Ave. and E 22nd St., about 3.4 miles driving. Medical offices are proposed within Sweetgrass, albeit in later phases of development (Parcel F). Medical uses are allowed in commercial parcels, although these would not be the primary use. We do not believe that the addition of Sweetgrass to Cheyenne will be detrimental to medical care in the region.

Community Parks: The Community Park gross area is proposed to be 79.6 acres. This area represents all of the formal public park dedication required for Sweetgrass. It should be noted that the service area for what is being referred to as "South Park," is the greater southeastern Cheyenne area, which includes unincorporated areas south of Interstate 80. Presumably, as other lands nearby (e.g., west of Highway 85) are annexed to Cheyenne, additional community parks in those areas will be dedicated, reducing the demand for South Park. Previous direction from the City Parks Department indicated that approximately 68 acres of unencumbered land was required, based on a cap of 5,000 residents. It should be noted that a portion of the park will be within BOPU water and sewer easements, as well as existing gas line easements. Preliminary calculations indicate that about 71 acres are outside of these easements, leaving about three acres for detention and stormwater conveyance, much of which will be required for the park itself. These figures will be updated as design progresses. Please refer to the Sketch Plan, as well as the "South Park Exhibit" included with the application for additional details.

Local and Neighborhood Parks: Because of the proposed Community Park, individual residential parcels are not obligated to provide additional park area. If constructed, local and neighborhood parks would be privately owned and maintained.

Trails and Greenways: Approximately 12.3 miles of Greenway trails are proposed within Sweetgrass (to be publicly maintained), along with an additional 11.0 miles of trails to be privately maintained in open space tracts. Greenway trails are generally along major rights of way and/or provide off-street connections between school tracts. The above figures exclude local trails to be constructed with various residential parcels. Please note that an underpass is proposed below College Drive, which will connect the Village Center to the LCCC, about halfway between Sweetgrass Drive and Cattle Drive.

APRIL 17, 2018



Attachment C